F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	102	6
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* 99(1&2)AC-R-2 CONTRACT NO. 60B97

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (90% FED. 10% STATE URBAN)	WILL COUNTY — ROADWAY WESTERN FRONTAGE ROAD (CONSTRUCTION TYPE CODE I000-2A)	SIGNING (CONSTRUCTION TYPE CODE Y002-1C)	STRUCTURE CULVERT (CONSTRUCTION TYPE CODE Y007)								
~~60600605~~	~~CONCRETE CURB, TYPE B~~	~~FOOT~~	~~13.5~~	~~13.5~~										
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	192.0	192.0										
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	160.0	160.0										
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	387.5	387.5										
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2										
63500105	DELINEATORS	EACH	62	62										
66500105	WOVEN WIRE FENCE, 4'	FOOT	2,368	2,368										
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	2,306	2,306										
66502400	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	FOOT	2,308	2,308										
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9										
67100100	MOBILIZATION	L SUM	1	1										
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1										
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1603	1603										
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3100	3100										
* 72000100	SIGN PANEL - TYPE 1	SQ FT	89		89									
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	200	200										
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	187		187									
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	13		13									
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	171	171										
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,728	18,728										
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	218	218										
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	107	107										
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	39	39										
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	38	38										
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	166	166										
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6										
* 78200500	BARRIER WALL MARKERS, TYPE C	EACH	25	25										
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2										
X0323260	SEDIMENT BASIN	EACH	2	2										
X0325561	CULVERTS TO BE GROUTED	CU YD	7	7										
X0712400	TEMPORARY PAVEMENT	SQ YD	3825	3825										
~~70106800~~	~~CHANGEABLE MESSAGE SIGN~~	~~CAL MO~~	~~9~~	~~9~~										
* X7030104	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 4 INCH	FOOT	29,268	29,268										
XX003669	BITUMINOUS SIDEWALK REMOVAL	SQ YD	88	88										
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1										
XX005656	INLET FILTER CLEANING	EACH	16	16										

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 WEST FRONTAGE ROAD AT IL 59
SECTION: 99(1&2)AC-R-2

SUMMARY OF QUANTITIES III

SCALE:
DRAWN BY: JB
DATE: 03/22/2007
CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
360 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/853-0300

..\SU000294.DGN,..\SU000290.DGN,..\TTB0026Z.DGN
3-22-2007, 8:53:00 T:\DOCUMENT\932790\CIVIL\DGN\SU0002BG.DGN
BONDHUJO
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63