

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	102	11
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS		
FED. AID PROJECT		CONTRACT NO. 60B97		

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)			TOTAL	56
STA.			UNIT	
EAST SIDE WFR	5007+41.55		12.0	
EAST SIDE WFR	5017+69.00		8.0	
EAST SIDE WFR	5018+47.30		11.0	
EAST SIDE WFR	5020+03.78		7.0	
EAST SIDE WFR	5022+35.84		9.0	
EAST SIDE WFR	5025+89.48		9.0	

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)			TOTAL	71
STA.			UNIT	
EAST SIDE WFR	5015+62.95		16.0	
EAST SIDE WFR	5016+27.23		21.0	
EAST SIDE WFR	5107+30.00		34.0	

25000210 SEEDING, CLASS 2A				TOTAL	6.00
		FROM STA.	TO STA.	SQ FT	ACRE
WFR LEFT		5500+00.00	5503+57.82	8029.90	0.18
WFR LEFT		5503+57.82	5504+96.12	2615.54	0.06
WFR LEFT		5504+96.12	5511+10.02	8095.01	0.19
WFR LEFT		5511+10.02	5515+98.81	7060.32	0.16
WFR LEFT		5515+98.81	5517+98.24	2991.74	0.07
WFR LEFT		5519+01.56	5521+00.10	3025.31	0.07
WFR LEFT		5521+00.10	5529+79.77	14057.20	0.32
WFR LEFT		5529+79.77	5535+00.57	13296.41	0.31
WFR LEFT		5535+00.57	5543+76.72	18728.60	0.43
WFR RIGHT		5496+64.22	5511+07.97	63068.47	1.45
WFR RIGHT		5511+07.97	5520+99.85	64912.89	1.49
WFR RIGHT		5520+99.85	5529+73.01	20553.83	0.47
WFR RIGHT		5530+06.55	5534+99.59	8401.55	0.19
WFR RIGHT		5534+99.59	5543+73.28	14221.00	0.33
WFR RIGHT		5026+91.22	5028+34.22	2857.92	0.07
RIVER CROSSING			SOUTH	519.49	0.01
			NORTH	866.98	0.02

25100630 EROSION CONTROL BLANKET				TOTAL	62080
		SQ FT	SQ YD		
STAGING	FOR TEMPORARY EROSION CONTROL SEEDING AREAS	305421.67	33935.7		
LANDSCAPING	FOR SEEDING, CLASS 2A AREAS	253302.16	28144.7		

25200110 SODDING, SALT TOLERANT				TOTAL	1060
		FROM STA.	SQ FT	SQ YD	
SEIL RD		4009+08.08	4951.18	550.13	
SEIL RD		4010+63.04	4591.83	510.20	

28000200 EARTH EXCAVATION FOR EROSION CONTROL						TOTAL	25
		STA.	LENGTH	WIDTH	DEPTH	CU FT	CU YD
STAGE I	WFR R	5022+77.74	20	8.00	2.00	320.00	11.85
	WFR R	5023+03.17	20	8.00	2.00	320.00	11.85

28000250 TEMPORARY EROSION CONTROL SEEDING						TOTAL	701
		FROM STA.	TO STA.	SQ FT	ACRES	POUND	
STAGE 1	EX WFR R	5003+55.00	5024+36.99	50953.80	1.17	116.97	
	EX WFR R	5026+91.22	5028+34.22	1591.66	0.04	3.65	
	PR WFR R	5519+24.91	SEIL	44994.96	1.03	103.29	
	PR WFR L	5519+24.91	SEIL	54272.92	1.25	124.59	
STAGE 2	PR WFR L	5500+00.00	5504+71.46	9583.30	0.22	22.00	
	PR WFR L	5504+71.46	5518+19.78	18934.71	0.43	43.47	
	PR WFR L	5518+96.38	5519+50.00	1621.07	0.04	3.72	
STAGE 3	PR WFR R	5003+55.00	5028+00.00	123469.25	2.83	283.45	

28000300 TEMPORARY DITCH CHECKS				TOTAL	30
		STA.	EACH		
STAGE I	WFR R	5005+00.00	1.00		
		5007+50.00	1.00		
		5010+00.00	1.00		
		5012+50.00	1.00		
		5015+00.00	1.00		
		5017+50.00	1.00		
		5020+00.00	1.00		
		5022+50.00	1.00		
	WFR R	5023+50.00	1.00		
		5541+75.00	1.00		
	WFR L	5543+50.00	1.00		
		5541+75.00	1.00		
		5543+50.00	1.00		
STAGE II	WFR L	5502+00.00	1.00		
		5506+50.00	1.00		
		5508+00.00	1.00		
		5509+50.00	1.00		
		5511+00.00	1.00		
		5512+50.00	1.00		
		5514+00.00	1.00		
		5515+50.00	1.00		
STAGE III	WFR R	5005+00.00	1.00		
		5007+50.00	1.00		
		5010+00.00	1.00		
		5012+50.00	1.00		
		5015+00.00	1.00		
		5017+50.00	1.00		
		5020+00.00	1.00		
		5022+50.00	1.00		
		5023+50.00	1.00		
		5025+50.00	1.00		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 55 WEST FRONTAGE ROAD AT IL 59
 SECTION: 99(1&2)AC-R-2

SCHEDULE OF QUANTITIES III

SCALE: _____ DRAWN BY: JB
 DATE: 03/22/2007 CHECKED BY: ACL

TENGL & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 205 N. MICHIGAN AVE. CHICAGO, IL 60601
 TELEPHONE: 312.581.8800

I:\SC0002\F4\JOB\...ATTB00262.DGN
 5-21-00 15:00:00
 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63