

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	•	WILL	102	12
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
• 99(1&2)AC-R-2		CONTRACT NO. 60B97		

28000400 PERIMETER EROSION BARRIER				TOTAL	5923
	STA FROM	STA TO	LENGTH	FOOT	
STI WFR L	5519+25.00	5519+25.00	70.42	70.42	
STI WFR L	5519+25.04	5523+19.50	383.27	383.27	
STI WFR L	5523+19.50	5529+70.84	651.34	651.34	
STI WFR L	5529+70.84	5529+70.84	10.00	10.00	
STI WFR L	5529+70.84	5529+83.87	13.03	13.03	
STI WFR L	5529+99.78	5537+79.73	807.73	807.73	
STI WFR L	5537+79.73	5544+35.45	671.46	671.46	
STI WFR R	5519+25.00	5523+22.50	411.83	411.83	
STI WFR R	5523+22.50	5530+40.83	718.35	718.35	
STI WFR R	5530+44.68	5532+96.90	245.04	245.04	
STI WFR R	5532+96.90	5532+96.90	3.00	3.00	
STI WFR R	5532+96.90	5536+27.47	319.98	319.98	
STI WFR R	5536+27.47	5536+27.47	3.00	3.00	
STI WFR R	5536+27.47	5537+60.47	129.09	129.09	
STI WFR R	5537+60.47	5544+19.73	658.70	658.70	
STI WFR R	4011+80.38	4011+80.38	42.74	42.74	
STI SEIL	4011+80.38	4010+79.41	108.56	108.56	
STI SEIL	4009+99.06	4009+09.23	89.84	89.84	
STI SEIL	4009+09.23	4009+09.23	43.08	43.08	
STII WFR	5500+00.00	5500+00.00	20.20	20.20	
STII WFR	5518+97.57	5519+50.00	122.44	122.44	
TOPSOIL STOCKPILE				5028+00.00	400.00
				400.00	

28000500 INLET AND PIPE PROTECTION				TOTAL	6
	STA.	OFFSET		EACH	
STI WFR	5523+94.58	RT		1.00	
STI WFR	5532+15.17	RT		1.00	
STI WFR	5534+00.11	RT		1.00	
STI WFR	5543+69.59	LT		1.00	
STI WFR	5543+69.67	RT		1.00	
STI WFR	5544+38.62	RT		1.00	

28000510 INLET FILTERS				TOTAL	16
	STA.	OFFSET		EACH	
STI WFR	5006+67.67	LT		1.00	
STI WFR	5017+83.73	LT		1.00	
STI WFR	5020+10.39	LT		1.00	
STI WFR	5023+02.04	LT		1.00	
DRIVEWAY	5518+23.32	LT		1.00	
DRIVEWAY	5518+98.78	LT		1.00	
DRIVEWAY	5519+33.50	LT		1.00	
STI WFR	5544+21.42	LT		1.00	
STI WFR	5544+20.67	RT		1.00	
STI WFR	5544+48.46	LT		1.00	
STI WFR	5544+45.73	RT		1.00	
STII WFR	5516+10.84	RT		1.00	
STII WFR	5516+45.79	LT		1.00	
STII WFR	5516+10.84	LT		1.00	
STII WFR	5513+19.61	LT		1.00	
STII WFR	5511+00.00	LT		1.00	

28100107 STONE RIPRAP, CLASS A4					TOTAL	70
	STA	OFFSET	AREA (SF)		SQ YD	
WFR	5523+94.36	RT	42.50		4.72	
WFR	5523+94.36	LT	85.00		9.44	
WFR	5532+08.00	RT	42.50		4.72	
WFR	5532+08.00	LT	85.00		9.44	
WFR	5534+00.00	RT	42.50		4.72	
WFR	5534+00.00	LT	85.00		9.44	
WFR	5544+44.00	RT	117.00		13.00	
WFR	5544+44.00	LT	134.00		14.89	

28200100 FILTER FABRIC FOR USE WITH RIPRAP					TOTAL	70
	STA	OFFSET	AREA (SF)		SQ YD	
WFR	5523+94.36	RT	42.50		4.72	
WFR	5523+94.36	LT	85.00		9.44	
WFR	5532+08.00	RT	42.50		4.72	
WFR	5532+08.00	LT	85.00		9.44	
WFR	5534+00.00	RT	42.50		4.72	
WFR	5534+00.00	LT	85.00		9.44	
WFR	5544+44.00	RT	117.00		13.00	
WFR	5544+44.00	LT	134.00		14.89	

28001000 AGGREGATE (EROSION CONTROL)								TOTAL	5
	STA.	LENGTH	WIDTH	DEPTH	CU FT	CU YD			
WFR STI SED BASIN	WFR R	5022+77.74	4	8.00	1.00	32.00	1.19		
WFR STI SED BASIN	WFR R	5023+03.17	4	8.00	1.00	32.00	1.19		

35102000 AGGREGATE BASE COURSE, TYPE B 8"					TOTAL	200
	STA.	SQ FT			SQ YD	
FIELD ENTRANCE	WFR L	5529+89.78	791.72		87.97	
FIELD ENTRANCE	WFR R	5529+89.78	601.92		66.88	
BIT SIDEWALK	RIVER CROSSING DRIVE / WFR	5518+93.70	405.90		45.10	

40603340 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70						TOTAL	5
	STA	LENGTH	WIDTH	DEPTH	SQ YD		TON
WFR CULVERT	5544+41.00	65.00	4	3.00	28.89		4.85

31102500 SUB-BASE GRANULAR MATERIAL, TYPE C 8"							TOTAL	4488
FROM STA.	TO STA.	LENGTH	WIDTH	LT & RT SIDES	SF		SQ YD	
5500+00	5544+87.97	4487.97	4.50	2.00	40391.73		4487.97	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 WEST FRONTAGE ROAD AT IL 59
SECTION: 99(1&2)AC-R-2

SCHEDULE OF QUANTITIES IV

SCALE: DRAWN BY: JB
DATE: 3/22/2007 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/LANDSCAPE ARCHITECTS
200 N. MICHIGAN AVE. CHICAGO, IL 60601
TEL: (312) 626-0900

\SC000075.DGN, \TTB000627.DGN
 4-23-2007 14:52:05
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63
 BONDHULLO