

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	102	13
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
* 99(1&2)AC-R-2		CONTRACT NO. 60B97		

40701996 HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 3/4"								TOTAL	12852
FROM STA.	TO STA.	LENGTH	WIDTH 1	WIDTH 2	THEO. AREA	ACT. AREA	SQ YD		
WFR	5500+00.00	5503+00.00	300.00	31.53	24.00	8329.50		925.50	
WFR	5503+00.00	5543+46.62	4046.62	24.00	24.00	97118.88		10790.99	
WFR	5543+46.62	5544+55.00					3963.77	440.42	
WFR DRIVE	5517+74.11	5519+27.55					6258.12	695.35	

40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING						TOTAL	22
STA.	SQ FT	DEPTH	SQ YD				TON
W FRONT	5529+89.78	791.72	2.00	87.97			9.85
W FRONT	5529+89.78	601.92	2.00	66.88			7.49
RIVER CROSSING DRIVE/ WFR	5518+93.70	405.90	2.00	45.10			5.05

44000100 PAVEMENT REMOVAL					TOTAL	8736
FROM STA.	TO STA.	SQ FT				SQ YD
W. FRONTAGE RD	5006+90.75	5025+22.70	78626.08			8736.23

44000500 COMBINATION CURB AND GUTTER REMOVAL			TOTAL	658
			FOOT	
RIVER CROSSING DRIVE EB OUTSIDE			164.00	
RIVER CROSSING DRIVE MEDIAN			154.00	
RIVER CROSSING DRIVE WB OUTSIDE & WFR			340.00	

44004250 PAVED SHOULDER REMOVAL					TOTAL	870
FROM STA.	TO STA.	OFFSET		SQ YD		
5006+90.75	5024+36.38	LT		430.00		
5006+90.75	5028+00.00	RT		440.00		

48101500 AGGREGATE SHOULDERS, TYPE B 6"						TOTAL	447
FROM STA.	TO STA.	THEO. LENGTH	WIDTH	SQ FT			SQ YD
MOT STI WFR R	5004+24.31	5024+36.99	2012.68	2.00	4025.36		447.26

48101600 AGGREGATE SHOULDERS, TYPE B 8"									TOTAL	918
FROM STA.	TO STA.	THEO. LENGTH	ACT. LENGTH	WIDTH	SQ FT		SQ YD			
WFR L	5500+00.00	5517+74.11	1774.11		1.00	1774.11	197.12			
	5517+74.11			41.43	1.00	41.43	4.60			
	5519+27.55			75.42	1.00	75.42	8.38			
	5519+27.55	5529+73.01	1045.46		1.00	1045.46	116.16			
	5530+06.55	5543+76.62	1370.07		1.00	1370.07	152.23			
WFR R	5500+00.00	5513+01.82	1301.82		1.00	1301.82	144.65			
	5518+56.26	5529+73.01	1116.75		1.00	1116.75	124.08			
	5530+06.55	5543+73.28	1366.73		1.00	1366.73	151.86			
WFR AT SEIL TEMP			46.00		2.00	92.00	10.22			
			39.00		2.00	78.00	8.67			

48203009 HOT-MIX ASPHALT SHOULDERS, 3"										TOTAL	141
FROM STA.	TO STA.	WIDTH	LENGTH	SQ FT		SQ YD					
1-55 IMPACT ATT (WFR)	5026+96.25	5028+04.25	9.00	108.00	972.00	108.00					
1-55 IMPACT ATT (WFR)	5028+04.25	5028+29.24	12.00	25.00	300.00	33.33					

48203029 HOT-MIX ASPHALT SHOULDERS, 8"										TOTAL	3759
FROM STA.	TO STA.	THEO. LENGTH	ACT. LENGTH	WIDTH	SQ FT		SQ YD				
WFR L	5500+00.00	5517+74.11	1774.11		4.00	7096.44	788.49				
WFR L	5517+74.11			41.43	4.00	165.72	18.41				
WFR L	5519+27.55			75.42	4.00	301.68	33.52				
WFR L	5519+27.55	5529+73.01	1045.46		4.00	4181.84	464.65				
WFR L	5530+06.55	5543+76.62	1370.07		4.00	5480.28	608.92				
WFR R	5500+00.00	5513+01.82	1301.82		4.00	5207.28	578.59				
WFR R	5518+56.26	5529+73.01	1116.75		4.00	4467.00	496.33				
WFR R	5530+06.55	5543+73.28	1366.73		4.00	5466.92	607.44				
WFR R GUARDRAIL	5513+01.82	5518+56.26	554.44		VAR	1465.92	162.88				

50104300 CONCRETE HEADWALL REMOVAL				TOTAL	1
STA.	OFFSET			CU YD	
24" HEADWALL	5023+02.00	RT		0.75	

50105220 PIPE CULVERT REMOVAL				TOTAL	44
STA.				FOOT	
27" RCCP	5023+02.04			44.00	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 WEST FRONTAGE ROAD AT IL 59
SECTION: 99(1&2)AC-R-2

SCHEDULE OF QUANTITIES V

SCALE: _____ DRAWN BY: JB
DATE: 3/22/2007 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERING SURVEYING & DESIGN
285 N. MICHIGAN AVE. CHICAGO, IL 60610
TELEPHONE: 312.986.9900

\S:\00007\F\001\11100002.DWG
 4-23-2007 10:25:55
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63
 BONDHULLO