

SCHEDULE OF QUANTITIES

F.A.I. RATE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	102	16
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS		FED. AID PROJECT
* 99(1&2)AC-R-2				CONTRACT NO. 60897

78201000 TERMINAL MARKER - DIRECT APPLIED		TOTAL	2
STA.		EACH	
NB W. FRONTAGE RD	5513+35.84	1.00	
NB W. FRONTAGE RD	5518+23.34	1.00	

X0323260 SEDIMENT BASIN		TOTAL	2
STA.		EACH	
STAGE I WFR R	5022+77.74 RT	1.00	
WFR R	5023+03.17 RT	1.00	

X0712400 TEMPORARY PAVEMENT		TOTAL	3525
FROM STA. TO STA.		SQ FT	SQ YD
STAGE I NB W. FRNT RD	5004+24.31 5024+37.00	27123.69	3013.74
STAGE IIA RIVER CROSSING	5517+43.62 5518+33.23	1735.00	192.78
STAGE I SEIL ROAD	5544+55.00 5544+87.97	2869.00	318.78

X7030104 WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 4 INCH		TOTAL	29268
FROM STA.	TO STA.	THEO. LGT. ACT. LGT. MULT COLOR	FOOT
STII WFR SB EDGE	5003+52.55 5024+86.16	2258.72 1	WHITE 2258.72
STII WFR NB EDGE	5002+62.15 5025+22.82	2262.17 1	WHITE 2262.17
STII WFR CENTER	5003+52.55 5024+84.68	2133.94 2	YELLOW 4267.88
STIIA RCD CENTER		450 2	YELLOW 900.00
STIIA RCD CENTER STOP LINE		15 6	WHITE 90.00
STIIB RCD CENTER		450 2	YELLOW 900.00
STIIB RCD CENTER STOP LINE		15 6	WHITE 90.00
STIII WFR SB EDGE	5500+00.00 5517+74.91	1774.91 1	WHITE 1774.91
STIII WFR SB EDGE	5517+74.91 RADIUS RETURN	41.4 1	WHITE 41.40
STIII WFR SB EDGE	RADIUS RETURN 5519+28.92	75.46 1	WHITE 75.46
STIII WFR SB EDGE	5519+28.92 5521+20.22	191.3 1	WHITE 191.30
STIII WFR CENTER	5496+61.40 5517+97.70	2136.3 2	YELLOW 4272.60
STIII WFR CENTER	5518+70.37 5521+20.00	249.63 2	YELLOW 499.26
STIII WFR NB EDGE	5495+71.40 5521+19.79	2548.387 1	WHITE 2548.39
(RE-APPLICATIONS) 50% OF SUBTOTAL			9096.00

XX003669 BITUMINOUS SIDEWALK REMOVAL		TOTAL	88
		SQ YD	
		87.92	

Z0001050 AGGREGATE SUBGRADE 12"		TOTAL	17934
FROM STA. TO STA.		LENGTH AVG WDH.	SQ FT SQ YD
W/ SHLDR W. FRONTAGE RD	5500+00.00 5503+00.00	300.00 38.10	11428.50 1269.83
W/ SHLDR W. FRONTAGE RD	5503+00.00 5517+74.11	1474.11 34.33	50611.06 5623.45
W/ SHLDR W. FRONTAGE RD	5517+74.11 5519+27.55	153.44 29.17	4475.08 497.23
W/ SHLDR W. FRONTAGE RD	5519+27.55 5543+46.62	2419.07 34.33	83054.66 9228.30
W/ SHLDR W. FRONTAGE RD	5543+46.62 5543+76.62	30.00 35.91	1077.41 119.71
W/ CURB W. FRONTAGE RD	5543+76.62 5544+55.00	78.38	3546.62 394.07
RIVER CROSSING DRIVE	W. FRONTAGE RD 5517+74.11 5519+27.55		7213.44 801.49

Z0018500 DRAINAGE STRUCTURES TO BE CLEANED		TOTAL	7
STA.	OFFSET	EACH	
STI WFR	5006+67.67 LT	1.00	
STI WFR	5017+83.73 LT	1.00	
STI WFR	5020+10.39 LT	1.00	
STI WFR	5023+02.04 LT	1.00	
DRIVEWAY	5518+23.32 LT	1.00	
DRIVEWAY	5518+98.78 LT	1.00	
DRIVEWAY	5519+33.50 LT	1.00	

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3		TOTAL	5
		EACH	
ST I WFR R	5017+89.80	1.00	
ST I WFR R	5021+76.78	1.00	
ST I I-55 SHLDR	5028+04.35	1.00	
ST II WFR L	5024+10.00	1.00	
ST II WFR L	5022+00.00	1.00	

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3		TOTAL	2
		EACH	
STA. 5517+33.00 RT			
STA. 5514+85+00 RT			

70400100 TEMPORARY CONCRETE BARRIER		TOTAL	3100
FROM STA.	TO STA.	FOOT	
STAGE I	83+53.23 108+04.27	2460	
STAGE I	5017+89.80 5021+76.72	390	
STAGE II	5515+23.51 5517+16.61	200	
STAGE III	5514+85.00 5517+34.74	50	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER		TOTAL	200
FROM STA.	TO STA.	FOOT	
STAGE III	5514+85.00 5517+34.74 FROM STAGE II	200	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 WEST FRONTAGE ROAD AT IL 59
SECTION: 99(1&2)AC-R-2

SCHEDULE OF QUANTITIES VIII

SCALE: DRAWN BY: JB
DATE: 3/22/2007 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
385 N. MICHIGAN AVE. CHICAGO, IL 60611
TELEPHONE: 312.664.6000

\S:\CO007\F&D\...ATTB00762.DGN
 4-23-2007 10:32:41
 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63
 \S:\CO007\F&D\...ATTB00762.DGN
 4-23-2007 10:32:41
 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63