

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2007-013 RS	DuPAGE	12	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		URBAN 1000						
20201006	GRADING AND SHAPING SHOULDERS	UNIT	142	142						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	11						
40600300	AGGREGATE (PRIME COAT)	TON	36	36						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8						
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	490	490						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2106	2106						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1993	1993						
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	450	450						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	568	568						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
67100100	MOBILIZATION	L SUM	1	1						
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	17100	17100						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5700	5700						
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34200	34200						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	500	500						
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	22	22						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	120	120						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	120	120						
X0322256	TEMPORARY INFORMATION, SIGNING	EACH	51.4	51.4						

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT								

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 I-55: NORTH FRONTAGE ROAD  
 CLARENDON HILLS RD. TO CASS AVE.

PLOT DATE: 4/2/2007

4/2/2007  
8:31:48 AM  
D:\Projects\60C50\60C50.dwg