

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	18	18				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19				
40600300	AGGREGATE (PRIME COAT)	TON	84	84				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	23				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	470	470				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	450	450				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3605	3605				
42001300	PROTECTIVE COAT	SQ YD	117	117				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	41667	41667				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	350	350				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	587	587				
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	10	10				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	185	185				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	138	138				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	254	254				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	69	69				
55039700	STORM SEWERS TO BE CLEANED	FOOT	1000	1000				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000-2A				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16389	16389				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	437				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	22577	22577				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1458	1458				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	533	533				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	461	461				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5463	5463				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	437				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22577	22577				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1458	1458				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	533	533				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	461	461				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	482	482				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	400	400				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	818	818				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1803	1803				
XX002258	STRUCTURES TO BE ADJUSTED	EACH	5	5				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	94	94				
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	3	3				

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
U.S. 30
SUMMARY OF QUANTITIES

4/11/2007 10:41:00 AM