

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
531	40X-RS-4	WILL	18	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	330	330			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15			
40600300	AGGREGATE (PRIME COAT)	TON	71	71			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22	22			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1988	1988			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	106	106			
40600990	TEMPORARY RAMP	SQ YD	106	106			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	464	464			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2982	2982			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	35500	35500			
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2071	2071			
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	415	415			
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	225	225			
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	890	890			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1300	1300			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2			
67100100	MOBILIZATION	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8650	8650			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	42495	42495			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	110	110			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17050	17050			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	42495	42495			

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	110	110			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	287	287			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	110	110			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52			

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 MANHATTAN-MONEE ROAD  
 SUMMARY OF QUANTITIES

4/13/2007 09:50:00 AM C:\Users\jgarcia\Documents\1020100010001000.mxd