

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	136 RS-4	LAKE	25	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	40	40				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15				
40600300	AGGREGATE (PRIME COAT)	TON	70	70				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22	22				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2000	2000				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1380	1380				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	720	720				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3000	3000				
42001300	PROTECTIVE COAT	SQ YD	350	350				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	34600	34600				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1500	1500				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	3200	3200				
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	50	50				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1370	1370				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	595	595				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	225	225				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	160	160				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	31	31				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5				
67100100	MOBILIZATION	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5500	5500				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	400	400				

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26700	26700				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2000	2000				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	600	600				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	350	350				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	13000	13000				
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	400	400				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26700	26700				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2000	2000				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	600	600				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	350	350				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	370	370				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	240	240				
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1900	1900				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	257	257				
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	350	350				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	23	23				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				

* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

4/25/2007 09:40:13 AM C:\PLOT\136RS4\136RS4.DWG