

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES 100% STATE	1000-2A	BRIDGE REPAIR SFTY-2A		
20201006	GRADING AND SHAPING SHOULDERS	UNIT	471	471			
21400100	GRADING AND SHAPING DITCHES	FOOT	21693	21693			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	63	63			
40600300	AGGREGATE (PRIME COAT)	TON	313	313			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	47	47			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	635	635			
40600990	TEMPORARY RAMP	SQ YD	635	635			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2668	2668			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1141	1141			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	204	204			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	13120	13120			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	156,273	156,273			
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	7,938	7,938			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3,907	3,907			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	2,345	2,345			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,563	1,563			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1884	1884			
58700300	CONCRETE SEALER	SQ FT	7360		7360		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	50	50			
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	220	220			
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	220	220			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES 100% STATE	1000-2A	BRIDGE REPAIR SFTY-2A		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13389	13389			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1570	1570			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	108025	108025			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5058	5058			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	132	132			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	44835	44835			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1570	1570			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	108025	108025			
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5058	5058			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	132	132			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1470	1470			
*78200405	GUARDRAIL MARKERS	EACH	4	4			
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1323	1323			
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	490	490			
X0301424	SILICONE JOINT SEALER	FOOT	172		172		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	75		75		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	40		40		
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	1820	1820			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6154	6154			
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	2		2		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. RTE. 846/IL 53 (CHICAGO ST.)
MANHATTAN RD. TO OLD ELM RD.

3/10/2007 8:48:53 AM C:\PLOT\846-01020209.m32