CONTRACT NO. 62656

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	14 RS-4	WILL	33	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	URBAN 1000	CONSTRUCTION TYPE CODE (Y031-1F): US RTE 30 AT RENWICK ROAD	US RTE 30 AT ESSINGTON ROAD	US RTE 30 AT VOYAGER LN.	US RTE 30 AT HENNEPIN DR.
20201006	GRADING AND SHAPING SHOULDERS	UNIT	80	80				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12	12				
40600300	AGGREGATE (PRIME COAT)	TON	61	61				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	341	341				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	89	89				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2967	2967				
42001300	PROTECTIVE COAT	SQ YD	67	67				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	31227	31227				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200				
44002215	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 3/4"	SQ YD	3186	3186				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	158	158				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	3150	3150				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	416	416				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4455	4455				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	80	80				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24400	24400				

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	URBAN 1000	CONSTRUCTION TYPE CODE (Y031-1F): US RTE 30 AT RENWICK ROAD	US RTE 30 AT ESSINGTON ROAD	US RTE 30 AT VOYAGER LN.	US RTE 30 AT HENNEPIN DR.
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1000	1000				
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	350	350				
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	200	200				
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4080	4080				
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	100	100				
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24400	24400				
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000				
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	350	350				
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200				
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	264	264				
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	40	40				
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4		1	1	1	1
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2450		1035	610	600	205
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	15		4	4	3	4
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	15		4	4	4	3
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	10		2	4	4	
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	17		4	4	4	5
*	88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4			1	1	2
*	88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	3		2			1
*	88030320	SIGNAL HEAD, LED, 3-FACE, 1-3 SECTION, 2-5 SECTION BRACKET MOUNTED	EACH	1					1

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

US ROUTE 30

IL 59 TO WEST OF I-55

PLOT DATE: 4/2/2007

4/2/2007
c:\projects\d301049\design_ov.dgn