

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	3034N-1	COOK	71	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			HSIP				F			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
				1000-2A 90% FED. 10% STATE	Y031-IF TRAFFIC 90% FED. 5% STATE 5% CITY	Y031-IF TRAFFIC 100% CITY	Y030-IE LIGHTING 80% FED. (STP-U) 20% CITY			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	70	70						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	307	307						
20101000	TEMPORARY FENCE	FOOT	744	744						
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5	5						
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5						
* 20101700	SUPPLEMENTAL WATERING	UNIT	17	17						
20200500	EARTH EXCAVATION (WIDENING)	CU YD	1504	1504						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	275	275						
20800150	TRENCH BACKFILL	CU YD	845	845						
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1865	1865						
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	200				200			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	24	24						
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	24	24						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	24	24						
25000750	MOWING	ACRE	0.5	0.5						
* 25200110	SODDING, SALT TOLERANT	SQ YD	1865	1865						
28000510	INLET FILTERS	EACH	42	42						
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2023	2023						
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	1650	1650						
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	137	137						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8						
40600300	AGGREGATE (PRIME COAT)	TON	40	40						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	88	88						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	99	99						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	16	16						

SUMMARY OF QUANTITIES			HSIP				F			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
				1000-2A 90% FED. 10% STATE	Y031-IF TRAFFIC 90% FED. 5% STATE 5% CITY	Y031-IF TRAFFIC 100% CITY	Y030-IE LIGHTING 80% FED. (STP-U) 20% CITY			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	824	824						
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	180	180						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	15337	15337						
42400800	DETECTABLE WARNINGS	SQ FT	60	60						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	8156	8156						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	390	390						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3481	3481						
44000600	SIDEWALK REMOVAL	SQ FT	10955	10955						
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	3938	3938						
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	756	756						
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	19	19						
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	367	367						
50300300	PROTECTIVE COAT	SQ YD	2479	2479						
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	340	340						
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	367	367						
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	190	190						
60107600	PIPE UNDERDRAINS 4"	FOOT	200	200						
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	22	22						
<del>60218300</del>	<del>MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID</del>	<del>EACH</del>	<del>5</del>	<del>5</del>						
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6						
60240327	INLETS, TYPE B, TYPE 23 FRAME AND GRATE	EACH	6	6						
60250200	CATCH BASINS TO BE ADJUSTED	EACH	10	10						
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	16	16						
60500040	REMOVING MANHOLES	EACH	2	2						
60500050	REMOVING CATCH BASINS	EACH	12	12						
60500060	REMOVING INLETS	EACH	2	2						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3481	3481						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9						
67100100	MOBILIZATION	L SUM	1	1						

1/10/2007

©NON-PARTICIPATING  
\*SPECIALTY ITEMS

Rev. 6-1-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
127TH ST. AT MAPLE AVE.

PLOT DATE: 1/10/2007