

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	3034 N-1	COOK	71	5
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	HSIP	F			CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	HSIP	F		
				1000-2A 90% FED. 10% STATE	Y031-IF TRAFFIC 90% FED. 5% STATE 5% CITY	Y030-IE LIGHTING 80% FED. (STP-U) 20% CITY						1000-2A 90% FED. 10% STATE	Y031-IF TRAFFIC 90% FED. 5% STATE 5% CITY	Y030-IE LIGHTING 80% FED. (STP-U) 20% CITY	
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1			89502380	REMOVE EXISTING HANDHOLE	EACH	6		6		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	566		566			89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1204		1204			A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	722		722			A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1368		1368			A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8			
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2317		2317			A2012001	TREE, AESCULUS X CARNE BRIOTTI (BRIOTTI HORSECHESTNUT), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	113		113			<del>B2003114</del>	<del>TREE, MALUS CORALBURST (CORALBURST CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED</del>	<del>EACH</del>	<del>5</del>	<del>5</del>			
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2			<del>B2003116</del>	<del>TREE, MALUS CORALBURST (CORALBURST CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED</del>	<del>EACH</del>	<del>2</del>	<del>2</del>			
87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT.	EACH	1		1			K1005863	TREE ROOT PRUNING	EACH	5	5			
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1		1			X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	1	1			
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2		2			X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103			
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8			<del>X0322453</del>	<del>WEED CONTROL, PRE-EMERGENT</del>	<del>POUND</del>	<del>100</del>	<del>100</del>			
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4		4			X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	100	100			
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	60		60			X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1447		1447		
87900200	DRILL EXISTING HANDHOLE	EACH	1		1			X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	42	42			
88000200	SIGNAL HEAD, 1-FACE, 3-SECTION, WITH ONE DUAL-INDICATION SECTION, MAST ARM MOUNTED	EACH	4		4			X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	13	13			
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	8		8			X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	550	550			
88500100	INDUCTIVE LOOP DETECTOR	EACH	10		10			X6020095	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2			
88600100	DETECTOR LOOP, TYPE I	FOOT	713		713			X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4		4			X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1473		1473		
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1			X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	637		637		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1			88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4		4		

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
127TH ST. AT MAPLE AVE.

PLOT DATE: 1/9/2007