

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS	WILL	334	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

100% STATE URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		PROP	EXIST	US 52	SIGNING	LIGHTING
				1000-2A	X271-2A	IL 59	IL 59	SFTY-2A		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	97							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	170							
20101000	TEMPORARY FENCE	FOOT	1312	1312						
20200100	EARTH EXCAVATION	CU YD	29571	29571						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	22614	22614						
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	5851	5851						
20800150	TRENCH BACKFILL	CU YD	3694	3694						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	21618	21618						
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	7924	7924						
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	24941	24941						
25000210	SEEDING, CLASS 2A	ACRE	1.67	1.67						
25000310	SEEDING, CLASS 4	ACRE	4.51	4.51						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	150	150						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	150	150						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	150	150						
25002024	SEEDING, CLASS 4B (MODIFIED)	ACRE	0.64	0.64						
25100115	MULCH, METHOD 2	ACRE	7.57	7.57						
25100630	EROSION CONTROL BLANKET	SQ YD	29927	29927						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	693	693						
28000300	TEMPORARY DITCH CHECKS	EACH	31	31						
28000500	INLET AND PIPE PROTECTION	EACH	4	4						
28000510	INLET FILTERS	EACH	272	272						
28100105	STONE RIPRAP, CLASS A3	SQ YD	156	156						
28100107	STONE RIPRAP, CLASS A4	SQ YD	132	132						
28200200	FILTER FABRIC	SQ YD	132	132						
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	3522	3522						
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	89656	89656						
35501330	HOT-MIX ASPHALT BASE COURSE, 11 1/2"	SQ YD	3262	3262						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	196	196						
40600300	AGGREGATE (PRIME COAT)	TON	144	144						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49.8	49.8						
40600895	CONSTRUCTING TEST STRIP	EACH	6	6						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1893	1893						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	741	741						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4079	4079						
42001300	PROTECTIVE COAT	SQ YD	2657	2657						
44000100	PAVEMENT REMOVAL	SQ YD	389	389						
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	126313	126313						
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	38472	38472						
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	30472	30472						
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	3779	3779						
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	644	644						
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	687	687						
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2171	2171						
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	325	325						
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	44	44						

\* SPECIALTY ITEMS  
 URBAN, 90% FEDERAL, 10% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55 (I-80 TO BLACK ROAD)  
 WIDENING AND RESURFACING

**SUMMARY OF QUANTITIES**  
 I

SCALE: N.T.S. DRAWN BY AG  
 DATE 03/22/07 CHECKED BY DDH

**TENG**  
 TENG & ASSOCIATES, INC.  
 ENGINEERS/ARCHITECTS/PLANNERS  
 CHICAGO, ILLINOIS

PLT DATE = #DATE#  
 FILE NAME = #FILE#  
 USER NAME = #USER#

S:\DOCUMENT\422361803\CIVIL\CON\S0614801.SHT

3-22-2007 13:16:27