

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS	WILL	334	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	PROP	EXIST	US 52	SIGNING	LIGHTING
					IL 59	IL 59	US 52		
60200905	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	4	4					
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	196	196					
60201320	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 21 FRAME AND GRATE	EACH	12	12					
60205010	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	41	41					
60205020	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 21 FRAME AND GRATE	EACH	11	11					
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60224035	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	3	3					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	270	270					
60500040	REMOVING MANHOLES	EACH	23	23					
60600605	CONCRETE CURB, TYPE B	FOOT	120	120					
60602200	CONCRETE GUTTER	FOOT	28196	28196					
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	687	687					
60621600	CONCRETE MEDIAN, TYPE SM	SQ FT	761	761					
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1050	1050					
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3					
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	5	5					
63200310	GUARDRAIL REMOVAL	FOOT	15503	15503					
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	125	125					
63500105	DELINEATORS	EACH	130	130					
63700805	CONCRETE BARRIER TRANSITION	FOOT	1558	1558					
63700900	CONCRETE BARRIER BASE	FOOT	21336	21336					
64200105	SHOULDER RUMBLE STRIP	FOOT	75472	75472					
67100100	MOBILIZATION	L SUM	1	1					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	54	54					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	237148	237148					
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	29036	29036					
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	36160	36160					
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	2357	2357					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	84411	84411					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	43852	43852					
72000100	SIGN PANEL - TYPE 1	SQ FT	17					17	
72000200	SIGN PANEL - TYPE 2	SQ FT	383					383	
72000300	SIGN PANEL - TYPE 3 (SEE NOTE)	SQ FT	2503					2503	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	9					9	
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	33					33	
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	2018					2018	
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1					1	
72600100	MILE POST MARKER ASSEMBLY	EACH	5					5	
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	257					257	
73000100	WOOD SIGN SUPPORT	FOOT	786					786	
73400100	CONCRETE FOUNDATIONS	CU YD	1.4					1.4	
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	2					2	
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2					2	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	77,547	77,547					

100% STATE URBAN

NOTE:
 TYPE 3 SIGN PANELS WHICH REQUIRE TYPE ZZ SHEETING WILL BE 100% PAID FOR BY STATE FUNDS. THE REST WILL BE PAID FOR BY 90% FEDERAL FUNDS AND 10% STATE FUNDS. A QUANTITY OF 1091 SQ FT OF ITEM NO. 72000300, SIGN PANEL - TYPE 3 REQUIRES TYPE ZZ RETROREFLECTIVE SHEETING.

* SPECIALTY ITEMS
 URBAN, 90% FEDERAL, 10% STATE (SEE NOTE)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 I-80 TO BLACK ROAD
 WIDENING AND RESURFACING

SUMMARY OF QUANTITIES III

SCALE: N.T.S. DRAWN BY AG
 DATE 03/22/07 CHECKED BY DDH

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS

Rev. 5-31-07

PLOT DATE: 03/22/07
 FILE NAME: I:\S06014001.DGN
 USER: MUSEER
 3-21-2007 10:05:05 AM
 SA DOCUMENT: 02381501\CIVIL\DWG\S06014001.DGN