CONTRACT NO. 62895

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS	WILL	334	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (100% STATE URBAN) ⚠	ROADWAY 1000-2A	PROP IL 59 099-4642 X271-2A	EXIST IL 59 099-0030 SFTY-2A	US 52 099-0139 SFTY-2A	SIGNING Y002-1C		LIGHTING Y030-1E
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	22325	22325						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4246	4246						
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	467	467						
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	22081	22081						
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	53266	53266						
* 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	34599	34599						
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	2502	2502						
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	3135	3135						
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	14955	14955						
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	2488	2488						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2567	2567						
* 78100300	REPLACEMENT REFLECTOR	EACH	2474	2474						
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	8639	8639						
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	22	22						
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	526	526						
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4						
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	31262	31262						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1081	1081						
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1635							1635
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	1							1
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	1							1
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	66.5							66.5
* 83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	4							4
* 84200800	POLE FOUNDATION, REMOVED	EACH	6							6
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6							6
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1126	1126						
X0322323	WEED CONTROL, TEASEL	GALLON	2.5	2.5						
X0322729	MATERIAL TRANSFER DEVICE	TON	47610	47610						
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	20	20						
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	272	272						
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	15	15						
* X0323879	SERVICE PATROL	CAL DA	330	330						
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	2268	2268						
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1973	1973						
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	382		382					
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	8	8						
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2						
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1864	1864						
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	1864	1864						
X0484300	MEDIAN INLET BOX REMOVAL	EACH	8	8						
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	25991	25991						
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	21619	21619						
X6370920	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	519	519						
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	19259	19259						
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1						
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	330	330						

* SPECIALTY ITEMS

~~** URBAN, 90% FEDERAL, 10% STATE~~ ⚠

⚠ Rev. 5-31-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (I-80 TO BLACK ROAD)
WIDENING AND RESURFACING

SUMMARY OF QUANTITIES
IV

SCALE: N.T.S. DRAWN BY AG

DATE 03/22/07 CHECKED BY DDH

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$

..\60PYAW0LDGN..\S0061W0LDGN..\S0061W0RLDGN
3:21:20070.15151516 S:\DOCUMENT\62895R01\CIVIL\DGN\S0061W0R4-SHT
CARCIAGAZ