

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|--------------|----------|------------------|-----------|
| 55 | 99 (1&2) WRS | WILL | 334 | 4 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY | | PROP | EXIST | US 52 | SIGNING | LIGHTING |
|----------|---|-------|----------------|---------|---------|-------|-------|---------|---------|----------|
| | | | | I000-2A | X271-2A | IL 59 | IL 59 | SFTY-2A | | |
| | | | | | | | | | | |
| | URBAN | | | | | | | | | |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 97 | 97 | | | | | | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 170 | 170 | | | | | | |
| 20101000 | TEMPORARY FENCE | FOOT | 1312 | 1312 | | | | | | |
| 20200100 | EARTH EXCAVATION | CU YD | 29571 | 29571 | | | | | | |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 22614 | 22614 | | | | | | |
| 20700420 | POROUS GRANULAR EMBANKMENT, SUBGRADE | CU YD | 5851 | 5851 | | | | | | |
| 20800150 | TRENCH BACKFILL | CU YD | 3694 | 3694 | | | | | | |
| 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION | SQ YD | 21618 | 21618 | | | | | | |
| 21101625 | TOPSOIL FURNISH AND PLACE, 6" | SQ YD | 7924 | 7924 | | | | | | |
| 21101815 | COMPOST FURNISH AND PLACE, 4" | SQ YD | 24941 | 24941 | | | | | | |
| 25000210 | SEEDING, CLASS 2A | ACRE | 1.67 | 1.67 | | | | | | |
| 25000310 | SEEDING, CLASS 4 | ACRE | 4.51 | 4.51 | | | | | | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 150 | 150 | | | | | | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 150 | 150 | | | | | | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 150 | 150 | | | | | | |
| 25002024 | SEEDING, CLASS 4B (MODIFIED) | ACRE | 0.64 | 0.64 | | | | | | |
| 25100115 | MULCH, METHOD 2 | ACRE | 7.57 | 7.57 | | | | | | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 29927 | 29927 | | | | | | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 693 | 693 | | | | | | |
| 28000300 | TEMPORARY DITCH CHECKS | EACH | 31 | 31 | | | | | | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 4 | 4 | | | | | | |
| 28000510 | INLET FILTERS | EACH | 272 | 272 | | | | | | |
| 28100105 | STONE RIPRAP, CLASS A3 | SQ YD | 156 | 156 | | | | | | |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 132 | 132 | | | | | | |
| 28200200 | FILTER FABRIC | SQ YD | 132 | 132 | | | | | | |
| 31101400 | SUB-BASE GRANULAR MATERIAL, TYPE B 6" | SQ YD | 3522 | 3522 | | | | | | |
| 35501316 | HOT-MIX ASPHALT BASE COURSE, 8" | SQ YD | 89656 | 89656 | | | | | | |
| 35501330 | HOT-MIX ASPHALT BASE COURSE, 11 1/2" | SQ YD | 3262 | 3262 | | | | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 196 | 196 | | | | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 144 | 144 | | | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS | TON | 49.8 | 49.8 | | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 6 | 6 | | | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 1893 | 1893 | | | | | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 741 | 741 | | | | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 4079 | 4079 | | | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 2657 | 2657 | | | | | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 389 | 389 | | | | | | |
| 44000163 | HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2" | SQ YD | 126313 | 126313 | | | | | | |
| 44000198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SQ YD | 38472 | 38472 | | | | | | |
| 44000920 | BITUMINOUS CONCRETE SHOULDER REMOVAL | SQ YD | 30472 | 30472 | | | | | | |
| 44002214 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2" | SQ YD | 3779 | 3779 | | | | | | |
| 44004510 | PORTLAND CEMENT CONCRETE SHOULDER REMOVAL | SQ YD | 644 | 644 | | | | | | |
| 44201761 | CLASS D PATCHES, TYPE I, 10 INCH | SQ YD | 687 | 687 | | | | | | |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SQ YD | 2171 | 2171 | | | | | | |
| 44201769 | CLASS D PATCHES, TYPE III, 10 INCH | SQ YD | 325 | 325 | | | | | | |
| 44201771 | CLASS D PATCHES, TYPE IV, 10 INCH | SQ YD | 44 | 44 | | | | | | |

* SPECIALTY ITEMS
 ** URBAN, 90% FEDERAL, 10% STATE

DATE = 03/22/07
 FILE NAME = 03/22/07 13:06:27
 PLOT SCALE = #SCALE#
 USER NAME = #USER#
 S:\DOCUMENT\02-36-1301\CIVIL\WORK\S0618140.DWG
 03/22/07 13:06:27

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55 (I-80 TO BLACK ROAD)
 WIDENING AND RESURFACING
SUMMARY OF QUANTITIES
I

SCALE: N.T.S.
 DATE 03/22/07
 DRAWN BY AG
 CHECKED BY DDH

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS