

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS	WILL	334	32
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

FROM STATION	TO STATION	EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL CU YD	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	TOPSOIL EXCAVATION AND PLACEMENT CU YD	PGE, SUBGRADE CU YD
BASINS (PRE-STAGE)								
334+00.00	RT	2572.0	390.0	2186.2	210.0	1976.2	390.0	0.0
350+00.00	LT	816.0	264.0	693.6	28.0	665.6	264.0	0.0
at IL-59		2200.0	328.0	1870.0	0.0	1870.0	328.0	0.0
PERMANENT DITCH CHECKS (PRE-STAGE)								
226+50.00	230+50.00	0.0	0.0	0.0	49.2	-49.2	0.0	0.0
PRE-STAGE TOTAL		5588.0	982.0	4749.8	287.2	4462.6	982.0	0.0

I-55 MAINLINE (STAGE I)								
FROM STATION	TO STATION	EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL CU YD	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	TOPSOIL EXCAVATION AND PLACEMENT CU YD	PGE, SUBGRADE CU YD
187+00.00	188+00.00	89.4	110.1	76.0	181.3	-105.3	21.6	0.0
188+00.00	189+00.00	119.5	154.9	101.6	297.8	-196.3	32.6	0.0
189+00.00	190+00.00	125.0	148.7	106.3	228.1	-121.9	24.5	0.0
190+00.00	191+00.00	116.9	142.3	99.3	161.7	-62.4	11.2	0.0
191+00.00	192+00.00	110.1	136.6	93.6	124.4	-30.8	0.0	0.0
192+00.00	193+00.00	101.4	130.9	86.2	140.4	-54.3	0.0	0.0
193+00.00	194+00.00	106.4	125.3	90.4	142.4	-51.9	0.0	0.0
194+00.00	195+00.00	118.5	171.7	100.7	67.7	33.0	0.0	97.9
195+00.00	196+00.00	128.1	194.4	108.9	0.0	108.9	0.0	172.9
196+00.00	197+00.00	135.2	157.2	114.9	0.0	114.9	0.0	130.5
197+00.00	198+00.00	134.9	117.0	114.6	23.5	91.1	0.0	55.5
198+00.00	199+00.00	134.1	84.6	114.0	48.0	66.0	0.0	0.0
199+00.00	200+00.00	132.5	79.4	112.6	51.2	61.4	0.0	0.0
200+00.00	201+00.00	126.5	89.4	107.6	26.8	80.8	0.0	34.2
201+00.00	202+00.00	129.6	116.0	110.2	17.3	92.9	7.6	59.5
202+00.00	203+00.00	129.9	144.0	110.4	52.4	58.0	29.9	76.1
203+00.00	204+00.00	132.1	150.7	112.3	81.8	30.5	37.1	50.7
204+00.00	205+00.00	151.2	140.6	128.5	92.1	36.5	33.7	0.0
205+00.00	206+00.00	165.7	100.2	140.8	62.6	78.2	25.5	0.0
206+00.00	207+00.00	176.1	60.0	149.7	25.9	123.8	11.4	0.0
207+00.00	208+00.00	183.8	40.1	156.2	8.7	147.5	4.8	0.0
208+00.00	209+00.00	153.5	11.5	130.5	0.0	130.5	0.0	0.0
209+00.00	210+00.00	125.3	0.0	106.5	0.2	106.3	0.0	0.0
210+00.00	211+00.00	174.0	0.0	147.9	0.2	147.7	0.0	0.0
211+00.00	212+00.00	221.3	0.0	188.1	0.0	188.1	0.0	0.0
212+00.00	213+00.00	198.4	11.4	168.6	0.0	168.6	0.0	0.0
213+00.00	214+00.00	168.3	26.8	143.0	0.0	143.0	0.0	0.0
214+00.00	215+00.00	160.6	34.5	136.6	0.0	136.6	0.0	0.0
215+00.00	216+00.00	137.8	41.2	117.2	3.9	113.3	0.0	0.0
216+00.00	217+00.00	125.3	61.0	106.5	12.8	93.6	0.0	0.0
217+00.00	218+00.00	177.8	77.8	151.1	8.9	142.2	0.0	0.0
218+00.00	219+00.00	198.1	77.7	168.4	0.0	168.4	0.0	0.0
219+00.00	220+00.00	164.0	77.7	139.4	0.1	139.2	0.0	0.0
220+00.00	221+00.00	147.6	77.8	125.5	4.2	121.3	0.0	0.0
221+00.00	222+00.00	111.5	112.4	94.8	4.0	90.8	0.0	61.5
222+00.00	223+00.00	81.9	148.0	69.7	0.0	69.7	0.0	125.3
223+00.00	224+00.00	81.2	150.5	69.0	0.0	69.0	0.0	130.5
224+00.00	225+00.00	105.4	114.8	89.6	27.2	62.4	0.0	66.7
225+00.00	226+00.00	125.1	77.8	106.4	64.9	41.5	0.0	0.0
226+00.00	227+00.00	124.8	77.8	106.1	65.1	41.0	0.0	0.0
227+00.00	228+00.00	104.6	77.8	89.0	53.3	35.6	0.0	0.0
228+00.00	229+00.00	80.8	77.8	68.7	47.9	20.8	0.0	0.0
229+00.00	230+00.00	82.9	77.8	70.4	40.4	30.1	0.0	0.0
230+00.00	231+00.00	84.7	77.8	72.0	34.5	37.5	0.0	0.0
231+00.00	232+00.00	84.6	77.8	71.9	35.6	36.3	0.0	0.0
232+00.00	233+00.00	82.6	77.8	70.3	42.5	27.8	0.0	0.0
233+00.00	234+00.00	81.1	77.8	68.9	48.8	20.1	0.0	0.0
234+00.00	235+00.00	82.9	77.8	70.5	41.8	28.6	0.0	0.0
235+00.00	236+00.00	84.9	77.8	72.1	32.9	39.3	0.0	0.0
236+00.00	237+00.00	96.6	83.8	82.1	16.8	65.2	0.0	8.8
237+00.00	238+00.00	114.7	87.6	97.5	0.0	97.5	0.0	13.4
238+00.00	239+00.00	123.8	84.5	105.2	0.0	105.2	0.0	8.3
239+00.00	240+00.00	130.5	80.7	111.0	0.7	110.3	0.0	3.7
240+00.00	241+00.00	129.6	77.8	110.2	1.3	108.8	0.0	0.0
241+00.00	242+00.00	145.3	77.8	123.5	0.6	122.9	0.0	0.0
242+00.00	243+00.00	132.5	77.8	112.6	8.3	104.3	0.0	0.0
243+00.00	244+00.00	98.8	77.8	84.0	22.6	61.4	0.0	0.0
244+00.00	245+00.00	92.7	77.8	78.8	34.9	43.9	0.0	0.0
245+00.00	246+00.00	90.5	96.5	76.9	20.7	56.2	0.0	41.9
246+00.00	247+00.00	89.9	126.2	76.4	0.0	76.4	0.0	99.5
247+00.00	248+00.00	91.4	139.9	77.6	0.0	77.6	0.0	116.0
248+00.00	249+00.00	96.9	110.2	82.3	25.3	57.0	0.0	58.5
249+00.00	250+00.00	94.9	77.8	80.7	51.3	29.4	0.0	0.0
250+00.00	251+00.00	92.0	77.8	78.2	52.3	25.9	0.0	0.0
251+00.00	252+00.00	93.5	100.5	79.4	26.4	53.1	0.0	41.6
252+00.00	253+00.00	93.6	120.0	79.6	0.0	79.6	0.0	79.4
253+00.00	254+00.00	92.2	120.0	78.4	0.0	78.4	0.0	90.3
254+00.00	255+00.00	91.3	103.0	77.6	23.2	54.4	0.0	52.5
255+00.00	256+00.00	94.7	77.8	80.5	43.7	36.8	0.0	0.0
256+00.00	257+00.00	97.0	77.8	82.4	44.5	38.0	0.0	0.0
257+00.00	258+00.00	91.0	77.8	77.4	54.2	23.2	0.0	0.0
258+00.00	259+00.00	88.7	77.8	75.4	57.1	18.2	0.0	0.0
259+00.00	260+00.00	92.5	77.8	78.6	49.9	28.7	0.0	0.0

FROM STATION	TO STATION	EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL CU YD	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	TOPSOIL EXCAVATION AND PLACEMENT CU YD	PGE, SUBGRADE CU YD
260+00.00	261+00.00	95.8	99.9	81.4	22.9	58.5	0.0	42.6
261+00.00	262+00.00	90.3	128.6	76.7	0.0	76.7	0.0	96.7
262+00.00	263+00.00	84.1	139.1	71.5	0.0	71.5	0.0	108.6
263+00.00	264+00.00	88.6	110.4	75.3	21.5	53.8	0.0	54.4
264+00.00	265+00.00	96.2	77.8	81.7	43.9	37.9	0.0	0.0
265+00.00	266+00.00	103.1	77.8	87.6	37.1	50.5	0.0	0.0
266+00.00	267+00.00	100.0	77.8	85.0	36.5	48.5	0.0	0.0
267+00.00	268+00.00	96.6	77.8	82.2	40.0	42.2	0.0	0.0
268+00.00	269+00.00	97.4	77.8	82.8	35.7	47.1	0.0	0.0
269+00.00	270+00.00	89.5	77.8	76.0	49.1	27.0	0.0	0.0
270+00.00	271+00.00	91.6	77.8	77.9	55.4	22.4	0.0	0.0
271+00.00	272+00.00	96.4	77.8	82.0	44.9	37.1	0.0	0.0
272+00.00	273+00.00	91.7	77.8	77.9	38.5	39.4	0.0	0.0
273+00.00	274+00.00	85.9	77.8	73.0	38.6	34.4	0.0	0.0
274+00.00	275+00.00	84.7	77.8	72.0	43.4	28.7	0.0	0.0
275+00.00	276+00.00	86.8	77.8	73.8	42.7	31.1	0.0	0.0
276+00.00	277+00.00	93.3	77.8	79.3	30.5	48.8	0.0	0.0
277+00.00	278+00.00	101.9	77.8	86.6	24.7	61.9	0.0	0.0
278+00.00	279+00.00	103.8	97.3	88.2	14.8	73.4	0.0	35.8
279+00.00	280+00.00	104.7	117.0	89.0	0.0	89.0	0.0	66.7
280+00.00	281+00.00	99.1	118.5	84.3	0.0	84.3	0.0	68.2
281+00.00	282+00.00	87.8	98.8	74.7	20.4	54.3	0.0	37.2
282+00.00	283+00.00	84.7	77.8	72.0	44.0	28.0	0.0	0.0
283+00.00	284+00.00	84.6	117.0	72.0	23.7	48.3	0.0	67.0
284+00.00	285+00.00	77.9	156.3	66.2	0.0	66.2	0.0	135.2
285+00.00	286+00.00	73.8	152.7	62.8	0.0	62.8	0.0	131.4
286+00.00	287+00.00	74.9	148.8	63.7	0.0	63.7	0.0	124.0
287+00.00	288+00.00	73.9	151.1	62.8	0.0	62.8	0.0	124.4
288+00.00	289+00.00	71.7	159.1	61.0	0.0	61.0	0.0	139.1
289+00.00	290+00.00	147.9	121.2	125.7	0.0	125.7	0.0	75.4
290+00.00	291+00.00	143.7	77.8	122.1	65.1	57.0	0.0	0.0
291+00.00	292+00.00	67.2	77.8	57.1	97.4	-40.3	0.0	0.0
292+00.00	293+00.00	79.2	77.8	67.4	50.1	17.2	0.0	0.0
293+00.00	294+00.00	98.2	77.8	83.5	23.9	59.6	0.0	0.0
294+00.00	295+00.00	131.0	77.8	111.4	6.0	105.4	0.0	0.0
295+00.00	296+00.00	213.5	38.9	181.4	0.0	181.4	0.0	0.0
296+00.00	297+00.00	195.8	38.9	166.5	0.2	166.2	0.0	0.0
297+00.00	298+00.00	93.1	77.8	79.1	29.6	49.6	0.0	0.0
298+00.00	299+00.00	66.6	77.8	56.6	74.9	-18.3	0.0	0.0
299+00.00	300+00.00	63.5	77.8	54.0	103.0	-49.0	0.0	0.0
300+00.00	301+00.00	62.6	77.8	53.2	136.8	-83.6		