

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2946	3368 A-N	COOK	74	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT: 62915				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000-1A 90% FED 10% STATE	RETAINING WALL SFTY-2A 90% FED 10% STATE	TRAFFIC SIGNAL Y031-IF 90% FED 5% STATE 5% CALUMET CITY	NEW SIDEWALK SFTY-1B 50% STATE 50% CALUMET CITY		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1136	1136					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2133	2133					
20101000	TEMPORARY FENCE	FOOT	600	600					
20101200	TREE ROOT PRUNING	EACH	15	15					
20200100	EARTH EXCAVATION	CU YD	2985	2985					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1181	1181					
20400800	FURNISHED EXCAVATION	CU YD	1927	1927					
20800150	TRENCH BACKFILL	CU YD	275	275					
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	14		14				
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	11400	11400					
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	926	926					
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	10736	10722	14				
* 25000312	SEEDING, CLASS 4A	ACRE	0.3	0.3					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	132	132					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	132	132					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	132	132					
* 25100630	EROSION CONTROL BLANKET	SQ YD	1606	1606					
* 25200110	SODDING, SALT TOLERANT	SQ YD	10736	10722	14				
* 25200200	SUPPLEMENTAL WATERING	UNIT	30	30					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200					
28000300	TEMPORARY DITCH CHECKS	EACH	14	14					
28000400	PERIMETER EROSION BARRIER	FOOT	3100	3100					
28000510	INLET FILTERS	EACH	7	7					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	74	74					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	446	446					
35501322	HOT-MIX ASPHALT BASE COURSE, 9 1/2"	SQ YD	3325	3325					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15					
40600300	AGGREGATE (PRIME COAT)	TON	71	71					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	11	11					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000-1A 90% FED 10% STATE	RETAINING WALL SFTY-2A 90% FED 10% STATE	TRAFFIC SIGNAL Y031-IF 90% FED 5% STATE 5% CALUMET CITY	NEW SIDEWALK SFTY-1B 50% STATE 50% CALUMET CITY		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	102	102					
40601005	HOT-MIX ASHPALT REPLACEMENT OVER PATCHES	TON	430	430					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	59	59					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1523	1523					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	192	192					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1538	620			918		
44000100	PAVEMENT REMOVAL	SQ YD	926	926					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	14286	14286					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1643	1643					
44000300	CURB REMOVAL	FOOT	971	971					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	921	921					
44000600	SIDEWALK REMOVAL	SQ FT	594	594					
44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	3069	3069					
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	505	505					
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	1911	1911					
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	253	253					
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	400	400					
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	665	665					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1380	1380					
50200100	STRUCTURE EXCAVATION	CU YD	19				19		
50300225	CONCRETE STRUCTURES	CU YD	17				17		
50300300	PROTECTIVE COAT	SQ YD	1025	1025					
* 51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	306				306		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1470				1470		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
WENTWORTH AVE. AT RIVER OAKS DR.

PLOT DATE: 3/27/2007

Rev. 6-7-07

3/27/2007