

F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	(4MFT)R	WINNEBAGO	353	29
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

Z0049800 RELOCATE EXISTING SURVEY MARKERS

EACH	LOCATION	OFFSET
IL 251		
1.0	359 + 99	244.5' LT
1.0	360 + 23	115.7' LT
1.0	360 + 36	88' LT
1.0	360 + 56	70' LT
1.0	360 + 86	62' LT
1.0	361 + 06	62' LT
1.0	365 + 70	62' LT
1.0	366 + 23	53.4' LT
1.0	366 + 96	48' LT
1.0	369 + 36	48' LT
1.0	369 + 61	42.6' LT
1.0	371 + 54	43.3' LT
1.0	371 + 96	50' LT
1.0	372 + 21	57' LT
1.0	372 + 35	66.5' LT
1.0	372 + 43	83.9' LT
1.0	372 + 54	115.7' LT
1.0	373 + 22	60.7' LT
1.0	373 + 46	46.7' LT
1.0	374 + 26	47' LT
1.0	375 + 31	47.4' LT
1.0	375 + 31	45.1' LT
1.0	376 + 22	45.2' LT
1.0	376 + 22	47.8' LT
1.0	376 + 34	47.8' LT
1.0	376 + 34	45.9' LT
1.0	376 + 63	46' LT
1.0	376 + 63	48' LT
1.0	376 + 76	48' LT
1.0	380 + 60	49.6' LT
1.0	381 + 50	46.3' LT
1.0	382 + 56	47.4' LT
1.0	382 + 96	45' LT
1.0	383 + 06	40' LT
1.0	383 + 26	40' LT
1.0	383 + 36	45' LT
1.0	383 + 96	43.6' LT
1.0	384 + 66	43.6' LT
1.0	385 + 56	60' LT
1.0	385 + 77	73.8' LT
1.0	386 + 77	54' LT
1.0	389 + 56	54.1' LT
1.0	390 + 54	48.5' LT
1.0	392 + 96	44.1' LT
1.0	395 + 31	44.1' LT
1.0	395 + 53	59.2' LT
1.0	395 + 60	79.3' LT
1.0	395 + 59	159.3' LT
1.0	395 + 68	159.5' LT
1.0	396 + 34	160.5' LT
1.0	396 + 36	160.5' LT
1.0	396 + 39	85.6' LT
1.0	396 + 61	60' LT
1.0	398 + 27	59.9' LT
1.0	399 + 57	48.9' LT
1.0	399 + 97	42.6' LT
1.0	401 + 58	39' LT
1.0	401 + 88	45.9' LT
1.0	402 + 77	44.9' LT
1.0	403 + 12	47.4' LT
1.0	403 + 50	69.9' LT
1.0	403 + 54	134.9' LT
1.0	404 + 12	56.2' LT
1.0	404 + 17	45.3' LT
1.0	404 + 32	38.2' LT
1.0	405 + 12	38' LT
1.0	405 + 25	40.3' LT
1.0	357 + 77	46.1' RT
1.0	358 + 52	55' RT
1.0	358 + 80	66' RT
1.0	360 + 86	58' RT
1.0	361 + 16	52' RT
1.0	361 + 46	48.5' RT
1.0	362 + 21	48' RT
1.0	367 + 66	48' RT
1.0	367 + 76	40.3' RT
1.0	368 + 16	40.3' RT
1.0	368 + 26	48' RT
1.0	371 + 37	48' RT

Z0049800 RELOCATE EXISTING SURVEY MARKERS

EACH	LOCATION	OFFSET
IL 251		
1.0	372 + 04	369.1' RT
1.0	372 + 07	307.5' RT
1.0	372 + 23	229.2' RT
1.0	372 + 61	86.7' RT
1.0	372 + 76	66' RT
1.0	373 + 43	40.3' RT
1.0	375 + 41	40.3' RT
1.0	375 + 41	42' RT
1.0	376 + 01	42' RT
1.0	376 + 11	45' RT
1.0	376 + 19	54' RT
1.0	376 + 22	105.3' RT
1.0	377 + 16	163.4' RT
1.0	377 + 17	149.6' RT
1.0	377 + 17	64.5' RT
1.0	377 + 21	59' RT
1.0	377 + 46	51' RT
1.0	377 + 76	48' RT
1.0	378 + 35	48' RT
1.0	380 + 04	39.4' RT
1.0	380 + 04	48.3' RT
1.0	381 + 38	48.9' RT
1.0	381 + 82	47.6' RT
1.0	381 + 92	52.4' RT
1.0	382 + 02	80.3' RT
1.0	382 + 66	55' RT
1.0	382 + 76	48' RT
1.0	383 + 76	48' RT
1.0	385 + 71	48' RT
1.0	386 + 06	48' RT
1.0	387 + 56	48' RT
1.0	387 + 71	57' RT
1.0	387 + 79	92.1' RT
1.0	388 + 44	53.9' RT
1.0	388 + 66	47' RT
1.0	388 + 86	44' RT
1.0	389 + 06	43' RT
1.0	389 + 72	42.6' RT
1.0	390 + 28	42.9' RT
1.0	391 + 09	43.3' RT
1.0	391 + 43	42.7' RT
1.0	391 + 97	43.3' RT
1.0	393 + 26	44' RT
1.0	394 + 46	44' RT
1.0	394 + 66	48' RT
1.0	395 + 26	48' RT
1.0	395 + 46	54' RT
1.0	395 + 63	80.7' RT
1.0	395 + 75	280.5' RT
1.0	396 + 38	59.5' RT
1.0	396 + 56	46' RT
1.0	396 + 66	43' RT
1.0	397 + 96	43' RT
1.0	399 + 41	42.9' RT
1.0	399 + 51	45' RT
1.0	399 + 62	56.8' RT
1.0	400 + 27	52.7' RT
1.0	400 + 46	44.6' RT
1.0	401 + 95	47.3' RT
1.0	403 + 54	50.6' RT
1.0	404 + 24	63.1' RT
1.0	404 + 36	56.9' RT
1.0	404 + 56	52.9' RT
1.0	404 + 97	49' RT
1.0	405 + 37	49' RT
1.0	405 + 37	47.5' RT
1.0	405 + 37	47.5' RT
145.0	TOTAL	

XX001135 PAVEMENT PATCHING SPECIAL

SQ. YD	LOCATION	OFFSET
IL 251		
44.4	364 + 14.00	LT
382.2	365 + 56.00 - 369 + 00.00	LT
36.7	369 + 27.00 - 369 + 60.00	LT
175.6	371 + 00.00 - 372 + 58.00	LT
162.2	372 + 72.00 - 374 + 18.00	LT
100.0	375 + 31.00 - 376 + 21.00	LT
23.3	377 + 33.00 - 377 + 54.00	LT
388.9	378 + 00.00 - 381 + 50.00	LT
45.0	381 + 50.00 - 382 + 31.00	LT

XX001135 PAVEMENT PATCHING SPECIAL

SQ. YD	LOCATION	OFFSET
IL 251		
51.1	382 + 31.00 - 382 + 77.00	LT
49.4	382 + 77.00 - 383 + 66.00	LT
37.8	383 + 66.00 - 384 + 00.00	LT
41.7	384 + 00.00 - 384 + 75.00	LT
70.0	386 + 10.00 - 386 + 73.00	LT
77.8	388 + 40.00 - 389 + 10.00	LT
217.8	390 + 72.00 - 392 + 68.00	LT
56.1	392 + 68.00 - 393 + 69.00	LT
72.2	393 + 69.00 - 394 + 34.00	LT
74.4	394 + 34.00 - 395 + 68.00	LT
70.0	395 + 68.00 - 396 + 31.00	LT
261.1	397 + 92.00 - 400 + 27.00	LT
142.2	400 + 27.00 - 401 + 55.00	LT
66.7	401 + 55.00 - 402 + 15.00	LT
81.1	402 + 15.00 - 403 + 61.00	LT
87.8	403 + 61.00 - 404 + 40.00	LT
HARRISON AVE		
84.4	7 + 81.00 - 8 + 57	LT
56.0	8 + 59.00	RT/LT
90.0	8 + 58.00 - 9 + 00	RT/LT
PEOPLES AVE		
40.0	157 + 85.00	RT/LT
68.7	158 + 57.00 - 159 + 60	LT
63.3	157 + 85.00 - 158 + 80	LT
BLACKHAWK PARK AVE		
29.0	88 + 85.00	RT/LT
72.0	88 + 40.00 - 89 + 48	LT
18TH AVE		
567.8	53 + 50.00 - 58 + 61	RT
61.3	58 + 61.00 - 59 + 53	RT
35.0	58 + 48.00	RT/LT
16TH AVE		
23.0	29 + 26.00	RT/LT
4006.1	TOTAL	

XX001386 SANITARY SEWERS, PVC, 8"

FOOT	LOCATION	OFFSET
IL 251		
106.00	359 + 21	LT
16.00	359 + 08	RT
415.00	359 + 87	RT
537.00	TOTAL	

XX001900 STORM SEWERS, TYPE 2 8" (FIELD TILE REPLACEMENT)

FOOT	LOCATION	OFFSET
IL 251		
133.0	384 + 45	RT
133.0	TOTAL	

XX003000 CLASS SI CONCRETE STEPS

CU. YD	LOCATION	OFFSET
IL 251		
2.50	369 + 50	RT
10.30	381 + 75	LT
3.08	383 + 16	LT
1.00	387 + 66	LT
1.00	391 + 15	RT
1.00	392 + 94	RT
10.93	401 + 78	RT
9.10	402 + 25	RT
1.00	402 + 68	RT
15.71	402 + 89	RT
7.17	403 + 23	RT
62.79	TOTAL	

XX004353 WATERMAIN RELOCATION

L. SUM	LOCATION	OFFSET	
IL 251			
0.08	361 + 31	23.6' RT	12" MAIN
0.08	371 + 75	47.8' RT	6" MAIN
0.08	372 + 99	38.7' LT	10" MAIN
0.08	373 + 17	38.7' LT	12" MAIN
0.08	376 + 93	30' RT	6" MAIN
0.08	386 + 10	48.2' LT	6" MAIN
0.08	387 + 93	34.3' RT	6" MAIN
0.08	396 + 16	33.7' RT	8" MAIN
0.08	396 + 15	45.3' LT	8" MAIN
0.08	396 + 27	1' LT	12" MAIN
0.08	400 + 06	34.4' RT	6" MAIN
0.08	403 + 94	33.7' LT	6" MAIN
0.08	404 + 03	43.6' RT	6" MAIN
1.00	TOTAL		

PLOT DATE = Fri Apr 27 10:55:40 2007
 FILE NAME = c:\p\proj\eta\216839\dl6898r.dgn
 PLOT SCALE = 1/8" = 1' IN.
 USER NAME = graham