

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5789	(33&40)-I-FR	ROCK ISLAND	31	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

20200100 EARTH EXCAVATION

CU YD	LOCATION			
	27th ST RT	19+58	-	20+ 95
472				
472.00	TOTAL			

21101625 TOPSOIL FURNISH AND PLACE, 6"

SQ YD	LOCATION			
	27th ST RT	19+58	-	20+ 95
972				
972.00	TOTAL			

25200100 SODDING

SQ YD	LOCATION			
	27th ST RT	19+58	-	20+ 95
972				
972.00	TOTAL			

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION			
	27th ST RT	20+52		56' RT
1		20+63		56' RT
1		20+63		74' RT
3.00	TOTAL			

31100910 SUB-BASE GRANULAR MATERIAL, TYPE A 12"

SQ YD	LOCATION			
	27th ST RT	19+58	-	20+ 95
572				
572.00	TOTAL			

40600625 LEVELING BINDER (MACHINE METHOD), N50

TONS	LOCATION				
	69th AVE CT LT & RT	200+60	-	200+ 67	TAPER
1		200+67	-	201+ 17	
9		201+17	-	201+ 23	TAPER
11.00	TOTAL				

40600982 HOT-MIX ASPHALT SURFACE REMOVAL, BUTT-JOINT

SQ YD	LOCATION			
	69th AVE CT LT & RT	200+33	-	200+ 49
75				
75.00	TOTAL			

40600985 PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION			
	69th AVE CT LT & RT	201+31	-	201+ 47
46				
46.00	TOTAL			

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50

TONS	LOCATION			
	27th ST RT	20+22	-	20+ 42
1				
	69th AVE CT LT & RT	200+33	-	201+ 47
49				
50.00	TOTAL			

42000201 PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)

SQ YD	LOCATION			
	27th ST RT	19+58	-	20+ 95
497				
497.00	TOTAL			

44000100 PAVEMENT REMOVAL

SQ YD	LOCATION			
	69th AVE CT RT	200+66	-	201+ 26
21				
21.00	TOTAL			

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION			
	27th ST RT	20+22	-	20+ 94
70				
70.00	TOTAL			

44200919 CLASS B PATCHES, TYPE II, 7 INCH

SQ YD	LOCATION			
	69th AVE CT RT	200+94		
8		200+94		
10	LT	200+94		
10	LT	201+31		
28.00	TOTAL			

44213200 SAW CUTS

FOOT	LOCATION				
	69th AVE CT RT	200+94			6' CLASS B PATCH
39		200+94			6' CLASS B PATCH
57	LT	200+94			6' CLASS B PATCH
60	RT	201+31			6' CLASS B PATCH
156.00	TOTAL				

50105220 PIPE CULVERT REMOVAL

FOOT	LOCATION				
	69th AVE CT RT	200+80	-	201+ 38	18" PIPE CULVERT
58					
58.00	TOTAL				

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

FOOT	LOCATION			
	27th ST RT	20+52	-	20+ 64
9				
9.00	TOTAL			

PLOT DATE = Wed Mar 21 08:51:09 2007
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = mgj11