

PAVEMENT REMOVAL SCHEDULE										
LOCATION	STATION		STATION	SQ YD	SQ YD	FOOT	SQ FT	FOOT	FOOT	LSUM
IL 75										
1	10138+30	TO	10160+00	0	0	0	0	0	0	0
2	10160+00	TO	10190+00	0	0	0	0	252	0	0
3	10190+00	TO	10205+00	0	0	0	0	0	0	0
4	10205+00	TO	10220+00	56	0	0	0	0	0	0
5	10220+00	TO	10235+00	0	0	20	0	218	37	0
6	10235+00	TO	10250+00	168	0	0	0	830	0	1
7	10250+00	TO	10265+00	133	0	0	0	377	78	0
8	10265+00	TO	10280+00	0	0	0	0	0	0	0
9	10280+00	TO	10295+00	0	0	0	0	75	0	0
10	10295+00	TO	10310+00	183	0	0	0	0	0	0
11	10310+00	TO	10325+00	0	0	0	0	0	0	0
12	10325+00	TO	10340+00	164	0	0	0	132	68	0
13	10340+00	TO	10355+00	0	0	0	0	0	0	0
14	10355+00	TO	10370+00	276	0	0	0	112	88	0
15	10370+00	TO	10385+00	0	0	0	0	0	0	0
16	10385+00	TO	10400+00	0	0	0	0	150	0	0
17	10400+00	TO	10430+00	0	0	0	0	0	0	0
18	10430+00	TO	10445+00	0	0	0	0	0	0	0
19	10445+00	TO	10460+00	0	0	0	0	385	0	0
20	10460+00	TO	10490+00	0	0	0	0	0	0	0
21	10490+00	TO	10520+00	0	0	0	0	1,060	0	0
22	10520+00	TO	10550+00	0	0	0	0	0	0	0
23	10550+00	TO	10580+00	0	0	0	0	0	0	0
24	10580+00	TO	10600+00	0	0	0	0	526	0	0
IL-26/CEDARVILLE RD				219	63	234	462	0	0	0
IL-75/CEDARVILLE RD				0	0	98	0	0	0	0
GOOD NEIGHBOR POLICY ROUTES				0	0	0	0	0	0	0
TOTAL				1,199	63	352	462	4,117	271	1

CULVERT SCHEDULE											
LOCATION	STATION		STATION	FOOT	EACH	FOOT	EACH	FOOT	EACH	FOOT	
IL 75											
1	10138+30	TO	10160+00	0	0	0	0	0	0	0	
2	10160+00	TO	10190+00	0	0	0	0	0	0	0	
3	10190+00	TO	10205+00	0	0	0	0	0	0	0	
4	10205+00	TO	10220+00	0	0	0	0	0	0	0	
5	10220+00	TO	10235+00	0	0	0	0	15	1	10	
6	10235+00	TO	10250+00	0	0	0	0	0	0	2	
7	10250+00	TO	10265+00	35	2	0	0	0	0	0	
8	10265+00	TO	10280+00	0	0	0	0	0	0	0	
9	10280+00	TO	10295+00	0	0	0	0	0	0	0	
10	10295+00	TO	10310+00	35	2	0	0	0	0	1	
11	10310+00	TO	10325+00	0	0	0	0	0	0	0	
12	10325+00	TO	10340+00	73	2	0	0	0	0	0	
13	10340+00	TO	10355+00	0	0	0	0	0	0	0	
14	10355+00	TO	10370+00	0	0	0	0	0	0	0	
15	10370+00	TO	10385+00	0	0	0	0	0	0	0	
16	10385+00	TO	10400+00	0	0	0	0	0	0	0	
17	10400+00	TO	10430+00	0	0	0	0	0	0	0	
18	10430+00	TO	10445+00	0	0	0	0	0	0	0	
19	10445+00	TO	10460+00	0	0	0	0	0	0	0	
20	10460+00	TO	10490+00	0	0	0	0	0	0	0	
21	10490+00	TO	10520+00	0	0	0	0	0	0	0	
22	10520+00	TO	10550+00	0	0	0	0	0	0	0	
23	10550+00	TO	10580+00	0	0	0	0	0	0	0	
24	10580+00	TO	10600+00	35	2	0	0	0	0	0	
IL-26/CEDARVILLE RD				0	0	0	0	0	0	0	
IL-75/CEDARVILLE RD				0	0	0	0	84	2	0	
GOOD NEIGHBOR POLICY ROUTES				0	0	0	0	0	0	0	
TOTAL				178	8	0	0	99	3	10	1

CULVERT REMOVAL SCHEDULE						
LOCATION	STATION		STATION	EACH	EACH	EACH
IL 75						
1	10138+30	TO	10160+00	0	0	0
2	10160+00	TO	10190+00	0	0	0
3	10190+00	TO	10205+00	0	0	0
4	10205+00	TO	10220+00	0	0	0
5	10220+00	TO	10235+00	1	0	0
6	10235+00	TO	10250+00	0	0	0
7	10250+00	TO	10265+00	0	1	0
8	10265+00	TO	10280+00	0	0	0
9	10280+00	TO	10295+00	0	0	0
10	10295+00	TO	10310+00	0	1	0
11	10310+00	TO	10325+00	0	0	0
12	10325+00	TO	10340+00	0	1	0
13	10340+00	TO	10355+00	0	0	0
14	10355+00	TO	10370+00	0	0	0
15	10370+00	TO	10385+00	0	0	1
16	10385+00	TO	10400+00	0	0	0
17	10400+00	TO	10430+00	0	0	0
18	10430+00	TO	10445+00	0	0	0
19	10445+00	TO	10460+00	0	0	0
20	10460+00	TO	10490+00	0	0	0
21	10490+00	TO	10520+00	0	0	0
22	10520+00	TO	10550+00	0	0	0
23	10550+00	TO	10580+00	0	0	0
24	10580+00	TO	10600+00	0	1	0
IL-26/CEDARVILLE RD				0	0	0
IL-75/CEDARVILLE RD				0	1	0
GOOD NEIGHBOR POLICY ROUTES				0	0	0
TOTAL				1	5	1

ACROSS-ROAD CULVERT DESIGN SCHEDULE - IL ROUTE 75

CULVERT #	CULVERT LOCATION	EXIST. STR#	PROP. STR#	TYPE OF WORK	PROPOSED CULVERT SIZE	LENGTH OF CULVERT	PAY ITEM	QUANTITY (FOOT)	EXISTING CULVERT SIZE	CULVERT REMOVAL LENGTH	PROPOSED TYPE OF CULVERT CONSTRUCTION	CULVERT END TREATMENT LEFT	PROPOSED TYPE OF CONSTRUCTION FOR END TREATMENT LEFT	CULVERT END TREATMENT RIGHT	PROPOSED TYPE OF CONSTRUCTION FOR END TREATMENT RIGHT	DELINEATORS (63500105) AND TYPE C DELINEATOR POST (X0320065)
CULVERT #1	10210+99.32			REPLACEMENT	PRECAST CONCRETE BOX CULVERT 3' X 3'	45'	54010303	45	3' X 2' BOX	42'	PRECAST BOX	BOX CULVERT END SECTION	PRECAST	BOX CULVERT END SECTION	PRECAST	2
CULVERT #4	10248+73.77			REPLACEMENT	PRECAST CONCRETE BOX CULVERT 4' X 4'	144'	54010404	144	5' X 6' BOX	77'	PRECAST BOX	4' X 4' PRECAST END SECTION	PRECAST	4' X 4' PRECAST END SECTION	PRECAST	2
CULVERT #5	10263+22.67		089-1102	REPLACEMENT	PRECAST CONCRETE BOX CULVERT 7' X 6'	50'	54010706	100	10' X 8' BOX	42'	PRECAST BOX	BOX CULVERT END SECTION	PRECAST	BOX CULVERT END SECTION	PRECAST	2
CULVERT #6	10306+90.06			REPLACEMENT	PIPE CULVERTS, TYPE 2 RCCP 42"	75'	54201297	75	7'X4' BOX	69'	PRECAST PIPE	42" FLARED END SECTION	PRECAST	2' DEEP SPECIAL DROP STRUCTURE (4'X4' DROP BOX)	CAST-IN-PLACE	2
CULVERT #7	10332+15.63		089-2020	REPLACEMENT	PRECAST CONCRETE BOX CULVERT 9' X 6'	48'	54010906	144	11' X 7' BOX	42'	PRECAST BOX	BOX CULVERT END SECTION	PRECAST	BOX CULVERT END SECTION	PRECAST	2
CULVERT #8	10357+11.85		089-2019	REPLACEMENT	PRECAST CONCRETE BOX CULVERT 9' X 6'	59'	54010906	177	2- 9' X 6' BOXES	43'	PRECAST BOX	BOX CULVERT END SECTION	PRECAST	BOX CULVERT END SECTION	PRECAST	2
CULVERT #9	10369+83.25	089-1058	089-1201	REPLACEMENT	PRECAST CONCRETE BOX CULVERT 5' X 3'	52'	54010503	104	5' X 3' BOX	42'	PRECAST BOX	BOX CULVERT END SECTION	PRECAST	BOX CULVERT END SECTION	PRECAST	2
TOTAL = 14																

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

SCHEDULES OF QUANTITIES

SCALE: DATE: 12/20/06

DRAWN BY JMC
CHECKED BY DWB

Thu Jan 18 2007 09:20:08 FILES