

| | | | | |
|------------------------------------|---------|---------------------------|--------------|-----------|
| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1279 | * | LASALLE | 43 | 3 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |
| *1-RS, (106.107)RS-2, 108 RS-1 & I | | | | |

SUMMARY OF QUANTITIES

| CODE NO. | CONSTRUCTION TYPE CODE | UNIT | 80% FED. 20% STATE TOTAL QUANTITY | Y007 | | |
|----------|---|--------|--|-----------------------------|---|---|
| | | | | 1000 ROADWAY QUANTITY | S.N. 050-2040 (EX S.N. 050-0154) QUANTITY | S.N. 050-2041 (EX S.N. 050-0153) QUANTITY |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 57 | | 42 | 15 |
| 20100500 | TREE REMOVAL, ACRES | ACRE | 0.4 | | 0.4 | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 32 | | 32 | |
| 20200100 | EARTH EXCAVATION | CU YD | 1877 | | 1370 | 507 |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 655 | | 489 | 166 |
| 20700220 | POROUS GRANULAR EMBANKMENT | CU YD | 2,295 | | 1,710 | 585 |
| 25000200 | SEEDING, CLASS 2 | ACRE | 1.03 | | 0.7 | 0.33 |
| 20700400 | POROUS GRANULAR EMBANKMENT, SPECIAL | CU YD | 600 | | 460 | 140 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 93 | | 63 | 30 |
| 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION | SQ YD | 673 | | 361 | 312 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 93 | | 63 | 30 |
| 25100635 | HEAVY DUTY EROSION CONTROL BLANKET | SQ YD | 899 | | 317 | 582 |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 93 | | 63 | 30 |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 410 | | 357 | 53 |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 4,089 | | 3,063 | 1,026 |
| 28200200 | FILTER FABRIC | SQ YD | 410 | | 357 | 53 |
| 31100910 | SUB-BASE GRANULAR MATERIAL, TYPE A 12" | SQ YD | 505 | | 310 | 195 |
| 35501324 | HOT-MIX ASPHALT BASE COURSE, 10" | SQ YD | 1,839 | | 1,030 | 809 |
| 35501332 | HOT-MIX ASPHALT BASE COURSE, 12" | SQ YD | 452 | | 278 | 174 |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 11,195 | 10,307 | 518 | 370 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 276 | 254 | 13 | 9 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 22 | 20 | 1 | 1 |
| 40600525 | LEVELING BINDER (HAND METHOD), N50 | TON | 37 | 34 | 2 | 1 |
| 40600625 | LEVELING BINDER (MACHINE METHOD), N50 | TON | 2,701 | 2,468 | 136 | 97 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 819 | 819 | | |
| 40600990 | TEMPORARY RAMP | SQ YD | 387 | 387 | | |
| 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 6,339 | 5,873 | 272 | 194 |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 378 | 378 | | |
| 44000152 | HOT-MIX ASPHALT SURFACE REMOVAL, 3/4" | SQ YD | 59,724 | 59,724 | | |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 8,436 | 8,436 | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 461 | | 292 | 169 |
| 44000198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SQ YD | 1,574 | 1,574 | | |
| 44004000 | PAVED DITCH REMOVAL | FOOT | 365 | | 365 | |

PLOT DATE = 3/23/2007
 FILE NAME = c:\projects\ap020061\designdgn
 USER NAME = schuchberg

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____