

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	108,109RS4	KENDALL	34	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVEMENT MARKING (CONT.)

LOCATION	THERMOPLASTIC									TEMPORARY						RAISED REFL PAVT MARKER EACH	SHORT TERM PVT MK METER	
	LTRS & SYM	100MM		150MM		200MM	300MM		600MM	LTRS & SYM	100MM	150MM		200MM	300MM			600MM
	WHITE SQ M	WHITE METER	YELLOW METER	YELLOW METER	WHITE METER	WHITE METER	WHITE METER	YELLOW METER	WHITE METER	WHITE SQ M	YELLOW METER	YELLOW METER	WHITE METER	WHITE METER	YELLOW METER			WHITE METER
21+595.1 - 21+682			152					15			152				15		12	106
MEDIAN			61														6	
DOUBLE CENTERLINE						40				2.94				34			3	
TURN LANE	2.94																	
STOPBAR									8							8		
CROSSWALK					32		29											
CROSSWALK (SOMONAUK)					24		22											
21+682 - 21+811.6			318					30			318				30		14	82
MEDIAN			61								61						6	
DOUBLE CENTERLINE						40				2.94				32			3	
TURN LANE	2.94																	
STOPBAR									8							8		
CROSSWALK					37		33											
CROSSWALK (SOMONAUK)					25		23											
21+811.6 - 21+950.6				260							260						22	52
DOUBLE CENTERLINE																		
EDGE LINES		245																
STOPBAR (PARK)									4									
21+950.6 - 22+205.5																		136
DOUBLE CENTERLINE				321							321						28	
EDGE LINES		507																
MEDIAN			360					27			360					27	19	
22+205.5 - 22+249				28							28							17
DOUBLE CENTERLINE																		
EDGE LINES		85															6	
TURN LANE	2.94					28				2.94				26			3	
STOPBAR									4							4		
22+565 - 22+700.1					60								60				20	400
SKIP DASH																	10	
MEDIAN			227					20									6	
TURN LANE	4.41					76				4.41				62				
LANE EDGE				130													12	
THRU LANES	10.47									10.47								
STOPBAR									16							16		
22+700.1 - 22+980					75								75				23	578
SKIP DASH																	30	
MEDIAN			754					122			754				122		7	
TURN LANE	4.41					86				4.41				62				
LANE EDGE				149													14	
EDGE LINES		223.5																
THRU LANES	10.47									10.47								
STOPBAR									16							16		
RIGHT TURN LANE	2.94									2.94							8	
ISLAND						168.5	29							168	29		8	
US 34 LEFT					18								18				5	308
SKIP DASH																	6	
TURN LANE	4.41					63				4.41					63			
LANE EDGE				122													12	
THRU LANES	10.47									10.47								
STOPBAR									14							14		
US 34 RIGHT					18								18				5	308
SKIP DASH																	6	
TURN LANE	4.41					64				4.41					64			
LANE EDGE				129													12	
THRU LANES	10.47									10.47								
STOPBAR									16							16		
TOTALS	100.71	2310	4997	55	513	812	334	265	178	99.24	3977	55	171	503	401	132	463	2559

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULES

SCALE: VERT. _____
HORIZ. _____

DRAWN BY _____
CHECKED BY _____