

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
786	(109,110,111)RS-3	LASALLE	20	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTRUCTION CODE:			
			100% STATE TOTAL QUANTITY	LASALLE COUNTY	LIVINGSTON COUNTY	LASALLE STRUCTURES
				I000	I000	SFTY-2A
20400800	FURNISHED EXCAVATION	CU YD	114	103	11	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	142	132	10	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	40,382	37,629	2,753	
40600300	AGGREGATE (PRIME COAT)	TON	1,009	940	69	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	75	70	5	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	125	117	8	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	12,189	11,365	824	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,567	2,047	520	
40600990	TEMPORARY RAMP	SQ YD	469	434	35	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	21,040	19,600	1,413	27
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	852	767	85	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	SQ YD	12,665	12,341	4	320
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	480	445	35	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,984	4,632	352	
48203020	HOT-MIX ASPHALT SHOULDERS 5 3/4"	SQ YD	26,855	24,267	2,588	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	4		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	3	1	
67100100	MOBILIZATION	L SUM	1	0.9	0.1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.9	0.1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	11	11		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19,592	18,427	1,165	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4		122.4	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	200,435	185,674	16,761	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	19,670	18,482	1,188	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	167	23	144	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,946	2,754	192	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4		122.4	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FT	2,132	2,132		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FT	267	267		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	144		144	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	200,303	183,542	16,761	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	19,403	18,215	1,188	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	23	23		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,064	993	71	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,064	993	71	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1	

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY