

|                       |         |                           |              |           |
|-----------------------|---------|---------------------------|--------------|-----------|
| F.A.U. RTE.           | SECTION | COUNTY                    | TOTAL SHEETS | SHEET NO. |
| 5952                  | 0-BR    | GRUNDY                    | 86           | 4         |
| STA.                  |         | TO STA.                   |              |           |
| FED. ROAD DIST. NO. 7 |         | ILLINOIS FED. AID PROJECT |              |           |

SUMMARY OF QUANTITIES

| CODE NO  | ITEM   | UNIT  | URBAN<br>TOTAL QUANTITY | 80% FEDERAL<br>20% STATE<br>0% CITY |  |                      |                                     |                                     |
|----------|--|-------|-------------------------|-------------------------------------|--|----------------------|-------------------------------------|-------------------------------------|
|          |  |       |                         | ROADWAY                             | NETTLE CR.<br>PR. 032-0107<br>EX. 032-0076 | RETAINING<br>WALL #1 | RETAINING<br>WALL #2<br>SN 032-8802 | RETAINING<br>WALL #3<br>SN 032-8803 |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER)                    | UNIT  | 341                     | 341                                 |  |                      |                                     |                                     |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER)                    | UNIT  | 18                      | 18                                  |  |                      |                                     |                                     |
| 20200100 | EARTH EXCAVATION   | CU YD | 2849                    | 2849                                |  |                      |                                     |                                     |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL              | CU YD | 1107                    |                                     |  | 280                  | 827                                 |                                     |
| 20300100 | CHANNEL EXCAVATION                                       | CU YD | 785                     | 785                                 |  |                      |                                     |                                     |
| 20400800 | FURNISHED EXCAVATION                                     | CU YD | 4470                    | 4470                                |  |                      |                                     |                                     |
| 20700400 | POROUS GRANULAR EMBANKMENT, SPECIAL                      | CU YD | 2265                    |                                     | 224  | 520                  | 1521                                |                                     |
| 20800150 | TRENCH BACKFILL  | CU YD | 1234                    | 1234                                |  |                      |                                     |                                     |
| 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION             | SQ YD | 4267                    | 4267                                |  |                      |                                     |                                     |
| 21101505 | TOPSOIL EXCAVATION AND PLACEMENT                         | CU YD | 3351                    | 3351                                |  |                      |                                     |                                     |
| 25000110 | SEEDING, CLASS 1A  | ACRE  | 0.6                     | 0.6                                 |  |                      |                                     |                                     |
| 25000210 | SEEDING, CLASS 2A  | ACRE  | 1.3                     | 1.3                                 |  |                      |                                     |                                     |
| 25000400 | NITROGEN FERTILIZER NUTRIENT                             | POUND | 171                     | 171                                 |  |                      |                                     |                                     |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT                           | POUND | 171                     | 171                                 |  |                      |                                     |                                     |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT                            | POUND | 171                     | 171                                 |  |                      |                                     |                                     |
| 25100630 | EROSION CONTROL BLANKET                                  | SQ YD | 9105                    | 9105                                |  |                      |                                     |                                     |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING                        | POUND | 1710                    | 1710                                |  |                      |                                     |                                     |
| 28000300 | TEMPORARY DITCH CHECKS                                   | EACH  | 30                      | 30                                  |  |                      |                                     |                                     |
| 28000400 | PERIMETER EROSION BARRIER                                | FOOT  | 1262                    | 1262                                |  |                      |                                     |                                     |
| 28000500 | INLET AND PIPE PROTECTION                                | EACH  | 11                      | 11                                  |  |                      |                                     |                                     |
| 28100107 | STONE RIPRAP, CLASS A4                                   | SQ YD | 1498                    | 197                                 | 1301                                       |                      |                                     |                                     |
| 28200200 | FILTER FABRIC  | SQ YD | 1498                    | 197                                 | 1301                                       |                      |                                     |                                     |
| 31102000 | SUB-BASE GRANULAR MATERIAL, TYPE C                       | CU YD | 203                     | 203                                 |  |                      |                                     |                                     |
| 40201000 | AGGREGATE FOR TEMPORARY ACCESS                           | TON   | 220                     | 220                                 |  |                      |                                     |                                     |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT)                        | TON   | 6.8                     | 6.8                                 |  |                      |                                     |                                     |
| 40600300 | AGGREGATE (PRIME COAT)                                   | TON   | 8.6                     | 8.6                                 |  |                      |                                     |                                     |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50              | TON   | 1486.1                  | 1486.1                              |  |                      |                                     |                                     |
| 40603230 | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50  | TON   | 361.5                   | 361.5                               |  |                      |                                     |                                     |
| 40603535 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON   | 241                     | 241.0                               |  |                      |                                     |                                     |
| 42001165 | BRIDGE APPROACH PAVEMENT                                 | SQ YD | 502                     |                                     | 502  |                      |                                     |                                     |
| 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH       | SQ YD | 36                      | 36                                  |  |                      |                                     |                                     |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH       | SQ YD | 120                     | 120                                 |  |                      |                                     |                                     |
| 44000100 | PAVEMENT REMOVAL   | SQ YD | 6179.7                  | 6179.7                              |  |                      |                                     |                                     |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL                                | SQ YD | 190                     | 190                                 |  |                      |                                     |                                     |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL                      | FOOT  | 364                     | 364                                 |  |                      |                                     |                                     |

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 6  
SUMMARY OF QUANTITIES

SCALE: VERT. NTS  
HORIZ. NTS  
DATE 3/19/07

DRAWN BY RGR  
CHECKED BY DDM

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
130 E. RANDOLPH STREET  
CHICAGO, ILLINOIS 60601  
JOB NO. 541



M:\S\1\66594\66594 - Nettle Creek\5166594.dgn 3/19/2007 5:23:53 PM  
 default