

| FAU RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|---------------|---------|------------------|-----------|
| 5645 | (116,117)RS-3 | BUREAU | 10 | 2 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | BLDGNO | FED. AID PROJECT | |

GENERAL NOTES

(Revised October 5, 2006)

THE THICKNESS OF HMA SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA IS PLACED.

THE HMA SURFACE OF ALL MAILBOX TURNOUTS, PRIVATE ENTRANCES, COMMERCIAL ENTRANCES, AND SIDE ROADS SHALL BE MADE NEATLY, IN A WORKMANLIKE MANNER, AND SHALL ACCURATELY CONFORM TO THE SHAPES AND DIMENSIONS SHOWN ON THE PLAN DETAILS. IF REQUIRED BY THE ENGINEER, THE CONTRACTOR SHALL BE REQUIRED TO SAW CUT THE HMA SURFACE TO CONFORM TO THE SHAPES AND DIMENSIONS SHOWN ON THE PLAN DETAILS. THIS WORK SHALL BE INCLUDED IN THE COST OF THE HMA SURFACE

EXCEPT AS NOTED ON THE PLANS, PAVEMENT GRADES SHOWN ARE AT THE TOP OF PAVEMENT SURFACES.

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS HMA LIFTS.

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

IN AREAS OF FURNISHED EXCAVATION, SEEDING, FERTILIZER, AND MULCH SHALL BE CONSTRUCTED TO SECTION 250 OF THE STANDARD SPECIFICATION. THIS WORK WILL NOT BE PAID FOR SEPERATLY, BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION.

ADDITIONAL LEVELING BINDER HAS BEEN ADDED TO THE PLANS IN CASE MORE OF THE EXISTING BITUMINOUS MATERIAL COMES OFF THE BRICK PAVEMENT DURING THE MILLING OPERATION

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS INCLUDED IN THESE PLANS.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

| | | |
|------------------------------|--------|---------------------------|
| GRANULAR MATERIALS | 2.05 | TONS / CU YD |
| BITUMINOUS MAT PRIME COAT | 0.08 | GAL / SQ YD OR |
| | 0.375 | GAL / SQ YD |
| AGGREGATE PRIME COAT | 0.002 | TONS / SQ YD |
| HMA RESURFACING | 112 | LBS / SQ YD / IN |
| SHORT TERM PAVEMENT MARKING | 10 | FT /100 FT OF APPLICATION |
| MIX FOR CRACKS, JTS & FLGWYS | 0.0003 | TONS / SQ YD |
| LEVEL BINDER (HAND METHOD) | 0.0005 | TONS / SQ YD |

ALL DAMAGE TO DEPARTMENT OWNED UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE. THIS SHALL INCLUDE ALL TEMPORARY REPAIRS REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS. SPLICING OF ELECTRIC CABLE SHALL NOT BE ALLOWED. ELECTRIC CABLE SHALL BE REPLACED FROM POLE TO POLE OR CONTROLLER.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: Paul Powell
DISTRICT STUDIES & PLANS ENGINEER

DATE: March 23, 2007

EXAMINED BY: Herbert K. Lunge
DISTRICT CONSTRUCTION ENGINEER

Matt Jensen
DISTRICT MATERIALS ENGINEER

Rama Anderson
DISTRICT OPERATIONS ENGINEER