

FAU RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5645	116,117RS-3	BUREAU	10	6
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

MAINLINE											
LOCATION	WIDTH	LENGTH	AREA	HMA LEVEL BIND (HM)	LEVEL BINDER (MM) N70	HMA SC MIX "D" N70	MIX CR JTS FLANGEWYS	BIT MATLS PR CT	AGG PR CT	TEMP RAMP	AGG SHLD TY B
STATION	FT	FT	SQ YD	TON	TON	TON	TON	GAL	TON	SQ YD	TON
0.00 TO 0.11	44	580.8	2839.5	1.4	119.3	238.5	0.9	227.2	5.7	24.4	
0.11 TO 0.55	32.41	2323.2	8366.1	20.6	493.0	702.8	2.5	669.3	16.7		
0.55 TO 0.61	38.25	316.8	1346.4	0.7	56.5	113.1	0.4	107.7	2.7		
0.61 TO 0.72	40.75	580.8	2629.7	1.3	110.4	220.9	0.8	210.4	5.3		
0.72 TO 0.97 - NO C & G	32	1320.0	4693.3	2.3	197.1	394.2	1.4	375.5	9.4		87.7
0.97 TO 1.34 - NO C & G	26.0	1953.6	5643.7	2.8	237.0	474.1	1.7	451.5	11.3	14.4	129.8
TOTALS		7075.2	25518.8	30.1	1249.8	2207.9	7.9	2102.7	52.6	40.1	224.0

REMOVAL ITEMS				
LOCATION	LENGTH	PVT WIDTH	HMA SURF	HMA SURF
		F-F C & G	REM 2 1/4"	REM 3/4"
	FT	FT	SQ YD	SQ YD
0.00 TO 0.11	580.8	44	2839.5	
0.11 TO 0.55	2323.2	32.41	8366.1	
0.55 TO 0.61	316.8	38.25	1346.4	
0.61 TO 0.72	316.8	40.75	1434.4	
0.72 TO 0.97 No C & G	1320	32		4693.3
0.97 TO 1.34 No C & G	1953.6	26		5643.7
TOTALS			14406.0	10647.2

PAVEMENT MARKING															
LOCATION	TYPE	THPL	THPL	THPL	THPL	THPL	TEMP	TEMP	TEMP	TEMP	TEMP	RAISED	SHORT	WORK	
		PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	REF	TERM	ZONE
		MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	PVT	PVT	PVT
		4"	4"	6"	6"	24"	4"	4"	6"	6"	24"		MKR	MKR	MKR
		YEL	WHITE	YEL	WHITE	WHITE	YEL	WHITE	YEL	WHITE	WHITE			REM	
		FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	EACH	FT	SQ FT	
0.00 TO 0.72				950.4					950.4				1140.48	380.16	
0.72 TO 1.0			2956.8	369.6				2956.8	369.6				443.52	147.84	
1.0 TO 1.20	NO PS SB/PS NB	1056.0	2112.0	264.0			1056.0	2112.0	264.0				316.8	105.6	
1.20 TO 1.34	PS SB/NO PS NB	739.2	1478.4	184.8			739.2	1478.4	184.8				221.76	73.92	
0.14 - W BOYD AVE	X-WALK				60					60			18	6	
0.20 - E THOMPSON ST	X-WALK				60					60			18	6	
0.53 BRYANT WOOD CIRCLE	X-WALK & STOP BAR				170	85				170	88		76.5	25.5	
0.85 BRYANT WOOD ST															
0.00 TO 1.34	TOTALS	1849.1	6743.6	1821.9	299	88	1849.1	6743.6	1821.9	299	88	88	2302.1	767.4	

• NOTE: X-WALKS WILL NOT HAVE LADDERS

3/23/2007 11:47:50 AM c:\projects\ed05606\detail.s.dgn