

FAU RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5645	(116,117)RS-3	BUREAU	10	7

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

SIDE ROAD & ENTRANCES							
LOCATION	MILE	RT/LT	INCIDENTAL	HMA	BIT	AGG	FUR EX CU YD
			HMA	SURF	MATLS	PR CT	
			SURF	REM	PR CT		
			TON	SQ YD	GAL	TON	
	0.04	RT	2.02	16	1.28	0.03	
	0.06	RT	3.15	25	2.00	0.05	
	0.09	RT	1.40	11	0.92	0.02	
	0.11	LT	3.15	25	2.00	0.05	
BOYD ST	0.14	RT	16.25	129	10.32	0.26	
	0.14	LT	4.54	37.08	2.97	0.07	
	0.16	LT	1.40	11	0.89	0.02	
E THOMPSON ST	0.20	LT	NO WORK				
	0.24	LT	4.54	36	2.88	0.07	
	0.25	LT	2.02	16	1.28	0.03	
	0.32	LT	5.60	44	3.56	0.09	
	0.34	RT	1.40	11	0.89	0.02	
	0.36	LT	3.15	25	2.00	0.05	
	0.41	RT	5.60	44	3.56	0.09	
	0.48	LT	11.20	89	7.11	0.18	
	0.50	RT	2.02	16	1.28	0.03	
BRYANT WOOD DR	0.53	RT	NO WORK				
	0.54	LT	3.15	25	2.00	0.05	
	0.57	RT	2.02	16	1.28	0.03	
	0.58	LT	1.40	11	0.89	0.02	
	0.61	LT	3.15	25	2.00	0.05	
	0.62	LT	3.15	25	2.00	0.05	
	0.68	LT	2.02	16	1.28	0.03	
	0.71	LT	2.02	16	1.28	0.03	
	0.72	RT	2.02	16	1.28	0.03	
	0.74	LT	2.02	16	1.28	0.03	
	0.78	RT	2.52	20	1.60	0.04	
	0.81	LT	2.02	16	1.28	0.03	
BRYANT BLVD	0.85	LT	16.25	129	10.32	0.26	2
	0.86	RT	11.20	89	7.11	0.18	
	0.87	LT	3.15	25	2.00	0.05	
	0.89	RT	2.02	16	1.28	0.03	
	0.94	LT	3.15	25	2.00	0.05	
	0.96	RT	3.15	25	2.00	0.05	
	0.97	LT	2.02	16	1.28	0.03	
	1.01	RT	3.15	25	2.00	0.05	
	1.03	RT	3.15	25	2.00	0.05	
	1.04	RT	2.52	20	1.60	0.04	
	1.07	RT	2.52	20	1.60	0.04	
	1.08	RT	3.15	25	2.00	0.05	
PENTECOASTAL CHURCH	1.10	LT	NO WORK				
	1.11	RT	3.15	25	2.00	0.05	
	1.16	RT	3.15	25	2.00	0.05	
	1.17	RT	2.52	20	1.60	0.04	
	1.17	RT	3.15	25	2.00	0.05	
	1.18	LT	6.78	54	4.30	0.11	
	1.21	RT	2.52	20	1.60	0.04	
	1.23	RT	3.15	25	2.00	0.05	
	1.24	LT	3.15	25	2.00	0.05	
	1.25	RT	2.52	20	1.60	0.04	
	1.26	LT	3.15	25	2.00	0.05	
TOTALS			187.00	1485.57	118.85	2.97	2.00

ADJUSTMENT ITEMS					
LOCATION	RT/LT	MH	INLET	WATER	COMB
		ADJ	ADJ	MAIN	C & G
				ADJ	REM & REP
		EACH	EACH	EACH	FOOT
	0.00				
BOYD ST	0.14				
	0.14	RT	1	1	10
E THOMPSON ST	0.20				
	0.20	RT/LT	1	1	10
	0.25	LT	1		
	0.31	LT	1		
	0.32	LT	1	1	10
	0.36	RT		1	10
	0.37	LT	1		
	0.41	RT	1		
	0.49	LT	1		
	0.50	LT		1	10
BRYANT WOOD DRIVE	0.53				
	0.56	RT/LT		2	20
	0.63	RT/LT		2	20
	0.65	RT/LT		2	20
TOTALS			8	10	1

3/23/2007 11:47:40 AM
c:\projects\ed05606\defal1s.dgn