

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-2)PATCHING	LASALLE	15	6

SCHEDULE

LOCATION		PASSING LANE						DRIVING LANE					
MILE POST	LANE	PATCHING		DOWEL BARS EACH	SAW CUTS FOOT	PAVE'T FABRIC SQ YD	TIE BARS EACH	PATCHING		DOWEL BARS EACH	SAW CUTS FOOT	PAVE'T FABRIC SQ YD	TIE BARS EACH
		TYPE II SQ YD	TYPE IV SQ YD					TYPE II SQ YD	TYPE IV SQ YD				
73.00	EB	8		20	48	8		8		20	48	8	
73.02	EB							8		20	48	8	
73.03	EB							8		20	48	8	
73.04	EB							8		20	48	8	
73.06	EB							8		20	48	8	
73.08	EB	8		20	48	8		8		20	48	8	
73.09	EB							13		20	56	13	
73.10	EB							8		20	48	8	
73.11	EB							8		20	48	8	
73.12	EB	13		20	56	13		13		20	56	13	
73.13	EB	13		20	56	13		13		20	56	13	
73.14	EB	8		20	48	8		8		20	48	8	
73.15	EB	8		20	48	8		8		20	48	8	
73.16	EB	8		20	48	8		8		20	48	8	
73.17	EB	8		20	48	8		8		20	48	8	
73.21	EB							8		20	48	8	
73.22	EB							8		20	48	8	
73.23	EB							15		20	58	15	
73.25	EB							8		20	48	8	
73.31	EB							8		20	48	8	
73.40	EB	11		20	52	11		11		20	52	11	
73.45	EB							11		20	52	11	
73.46	EB	8		20	48	8		8		20	48	8	
73.47	EB	13		20	56	13		13		20	56	13	
73.48	EB	8		20	48	8		8		20	48	8	
73.49	EB							8		20	48	8	
73.50	EB							8		20	48	8	
73.51	EB							11		20	52	11	
73.52	EB	11		20	52	11		11		20	52	11	
73.53	EB	11		20	52	11		11		20	52	11	
73.55	EB							8		20	48	8	
73.57	EB	11		20	52	11		11		20	52	11	
73.59	EB	11		20	52	11		11		20	52	11	
73.60	EB	11		20	52	11		11		20	52	11	
73.61	EB							8		20	48	8	
73.65	EB							11		20	52	11	
73.66	EB							11		20	52	11	
73.71	EB	11		20	52	11		11		20	52	11	
73.73	EB	11		20	52	11		11		20	52	11	
73.75	EB	8		20	48	8		8		20	48	8	
PAGE 1 SUBTOTAL		199		400	1016	199		383		800	2010	383	

Date: February 22, 2007
c:/projects/main08/cm302/details.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES
CLASS B PATCHING EB
FAI ROUTE 80 (I-80)
SECTION (50-2)PATCHING
LASALLE COUNTY