



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2007

SUBJECT: FAU Route 6717 (BUS 24)  
Section 35RS-5, 36RS-8  
Tazewell County  
Contract No. 68351  
Item No. 280, June 15, 2007 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 1 – 5 of the Schedule of Prices.
2. Revised sheets 1, 4 – 7, 20 – 22, 34, 39 – 42, 44, 46 – 50, 77, 84 and 87 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: J. E. Crowe, Region 3, District 4; Roger Driskell; Estimates; Design & Environment File

TBW:RS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68351

State Job # - C-94-054-03  
 PPS NBR - 4-00069-0000  
 County Name - TAZEWELL - -  
 Code - 179 - -  
 District - 4 - -  
 Section Number - 35RS-5,36RS-8

Project Number

Route  
 FAU 6717  
 FAU 6713

| Item Number | Pay Item Description  | Unit of Measure | Quantity                 | x | Unit Price | = | Total Price |  |
|-------------|-----------------------|-----------------|--------------------------|---|------------|---|-------------|--|
| X0325778    | SOL REACT SIL CONC TR | SQ YD           | 1,258.000                |   |            |   |             |  |
| X2503100    | MOWING                | UNIT            | 194.000                  |   |            |   |             |  |
| * X4067107  | POL LB MM IL4.75 N50  | TON             | 2,410.000                |   |            |   |             |  |
| Z0020800    | EROSION CONTROL CURB  | FOOT            | 550.000                  |   |            |   |             |  |
| Z0020805    | EROSION CONT CURB REM | FOOT            | 550.000                  |   |            |   |             |  |
| Z0075310    | TIE BARS 3/4          | EACH            | 9.000                    |   |            |   |             |  |
| 20201006    | GRADING & SHAP SHLDS  | UNIT            | 114.000                  |   |            |   |             |  |
| 28001000    | AGGREGATE - EROS CONT | TON             | 87.000                   |   |            |   |             |  |
| 40200800    | AGG SURF CSE B        | TON             | 21.000                   |   |            |   |             |  |
| 40201000    | AGGREGATE-TEMP ACCESS | TON             | 13.000                   |   |            |   |             |  |
| * 40600200  | BIT MATLS PR CT       | TON             | 62.000                   |   |            |   |             |  |
| * 40600300  | AGG PR CT             | TON             | 329.000                  |   |            |   |             |  |
| 40600895    | CONSTRUC TEST STRIP   | EACH            | 1.000                    |   |            |   |             |  |
| * 40600982  | HMA SURF REM BUTT JT  | SQ YD           | 3,084.000                |   |            |   |             |  |
| * 40600990  | TEMPORARY RAMP        | SQ YD           | 521.000                  |   |            |   |             |  |
|             |                       |                 | * REVISED : JUNE 1, 2007 |   |            |   |             |  |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68351

State Job # - C-94-054-03  
 PPS NBR - 4-00069-0000  
 County Name - TAZEWELL - -  
 Code - 179 - -  
 District - 4 - -  
 Section Number - 35RS-5,36RS-8

Project Number

Route  
 FAU 6717  
 FAU 6713

| Item Number | Pay Item Description | Unit of Measure | Quantity                 | x | Unit Price | = | Total Price |  |
|-------------|----------------------|-----------------|--------------------------|---|------------|---|-------------|--|
| 40603310    | HMA SC "C" N50       | TON             | 2,542.000                |   |            |   |             |  |
| * 40603540  | P HMA SC "D" N70     | TON             | 8,842.000                |   |            |   |             |  |
| 40800050    | INCIDENTAL HMA SURF  | TON             | 318.000                  |   |            |   |             |  |
| * 44000151  | HMA SURF REM 1/2     | SQ YD           | 20,377.000               |   |            |   |             |  |
| 44000152    | HMA SURF REM 3/4     | SQ YD           | 15,734.000               |   |            |   |             |  |
| * 44000155  | HMA SURF REM 1 1/2   | SQ YD           | 88,820.000               |   |            |   |             |  |
| 44000158    | HMA SURF REM 2 1/4   | SQ YD           | 8,390.000                |   |            |   |             |  |
| 44201369    | CL C PATCH T3 11     | SQ YD           | 47.000                   |   |            |   |             |  |
| * 44201371  | CL C PATCH T4 11     | SQ YD           | 69.000                   |   |            |   |             |  |
| * 44201389  | CL C PATCH T2 13     | SQ YD           | 26.000                   |   |            |   |             |  |
| 44201394    | CL C PATCH T3 13     | SQ YD           | 122.000                  |   |            |   |             |  |
| 44201396    | CL C PATCH T4 13     | SQ YD           | 163.000                  |   |            |   |             |  |
| 44201803    | CL D PATCH T2 13     | SQ YD           | 15.000                   |   |            |   |             |  |
| * 44201807  | CL D PATCH T3 13     | SQ YD           | 60.000                   |   |            |   |             |  |
| 44201833    | CL D PATCH T4 15     | SQ YD           | 65.000                   |   |            |   |             |  |
|             |                      |                 | * REVISED : JUNE 1, 2007 |   |            |   |             |  |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68351

State Job # - C-94-054-03  
 PPS NBR - 4-00069-0000  
 County Name - TAZEWELL - -  
 Code - 179 - -  
 District - 4 - -  
 Section Number - 35RS-5,36RS-8

Project Number

Route  
 FAU 6717  
 FAU 6713

| Item Number | Pay Item Description  | Unit of Measure | Quantity                 | x | Unit Price | = | Total Price |  |
|-------------|-----------------------|-----------------|--------------------------|---|------------|---|-------------|--|
| * 44201851  | CL D PATCH T2 17      | SQ YD           | 965.000                  |   |            |   |             |  |
| 44201855    | CL D PATCH T3 17      | SQ YD           | 159.000                  |   |            |   |             |  |
| * 44201857  | CL D PATCH T4 17      | SQ YD           | 615.000                  |   |            |   |             |  |
| 44300200    | STRIP REF CR CON TR   | FOOT            | 1,220.000                |   |            |   |             |  |
| * 48101200  | AGGREGATE SHLDS B     | TON             | 1,559.000                |   |            |   |             |  |
| * 60255500  | MAN ADJUST            | EACH            | 1.000                    |   |            |   |             |  |
| 63000000    | SPBGR TY A            | FOOT            | 2,250.000                |   |            |   |             |  |
| 63100045    | TRAF BAR TERM T2      | EACH            | 6.000                    |   |            |   |             |  |
| 63100070    | TRAF BAR TERM T5      | EACH            | 2.000                    |   |            |   |             |  |
| 63100085    | TRAF BAR TERM T6      | EACH            | 2.000                    |   |            |   |             |  |
| 63100167    | TR BAR TRM T1 SPL TAN | EACH            | 6.000                    |   |            |   |             |  |
| 63200310    | GUARDRAIL REMOV       | FOOT            | 2,806.000                |   |            |   |             |  |
| 63500105    | DELINEATORS           | EACH            | 35.000                   |   |            |   |             |  |
| 66700205    | PERM SURV MKRS T1     | EACH            | 5.000                    |   |            |   |             |  |
| 66700605    | PERM SURVEY TIES      | EACH            | 4.000                    |   |            |   |             |  |
|             |                       |                 | * REVISED : JUNE 1, 2007 |   |            |   |             |  |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68351

State Job # - C-94-054-03  
 PPS NBR - 4-00069-0000  
 County Name - TAZEWELL - -  
 Code - 179 - -  
 District - 4 - -  
 Section Number - 35RS-5,36RS-8

Project Number

Route

FAU 6717

FAU 6713

| Item Number | Pay Item Description  | Unit of Measure | Quantity                 | x | Unit Price | = | Total Price |  |
|-------------|-----------------------|-----------------|--------------------------|---|------------|---|-------------|--|
| 67000400    | ENGR FIELD OFFICE A   | CAL MO          | 3.000                    |   |            |   |             |  |
| 67100100    | MOBILIZATION          | L SUM           | 1.000                    |   |            |   |             |  |
| 70100420    | TRAF CONT-PROT 701411 | EACH            | 4.000                    |   |            |   |             |  |
| 70101220    | TC-PROT 701411 SPL    | EACH            | 1.000                    |   |            |   |             |  |
| 70101900    | TRAF CONT & PROT D1   | L SUM           | 1.000                    |   |            |   |             |  |
| 70102620    | TR CONT & PROT 701501 | L SUM           | 1.000                    |   |            |   |             |  |
| 70102622    | TR CONT & PROT 701502 | L SUM           | 1.000                    |   |            |   |             |  |
| 70102630    | TR CONT & PROT 701601 | L SUM           | 1.000                    |   |            |   |             |  |
| 70102635    | TR CONT & PROT 701701 | L SUM           | 1.000                    |   |            |   |             |  |
| 70106800    | CHANGEABLE MESSAGE SN | CAL MO          | 8.000                    |   |            |   |             |  |
| 70300100    | SHORT-TERM PAVT MKING | FOOT            | 16,166.000               |   |            |   |             |  |
| * 70300210  | TEMP PVT MK LTR & SYM | SQ FT           | 1,569.000                |   |            |   |             |  |
| 70300220    | TEMP PVT MK LINE 4    | FOOT            | 78,042.000               |   |            |   |             |  |
| 70300240    | TEMP PVT MK LINE 6    | FOOT            | 5,480.000                |   |            |   |             |  |
| 70300250    | TEMP PVT MK LINE 8    | FOOT            | 12,835.000               |   |            |   |             |  |
|             |                       |                 | * REVISED : JUNE 1, 2007 |   |            |   |             |  |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68351

State Job # - C-94-054-03  
 PPS NBR - 4-00069-0000  
 County Name - TAZEWELL - -  
 Code - 179 - -  
 District - 4 - -  
 Section Number - 35RS-5,36RS-8

Project Number

Route  
 FAU 6717  
 FAU 6713

| Item Number | Pay Item Description  | Unit of Measure | Quantity                 | x | Unit Price | = | Total Price |  |
|-------------|-----------------------|-----------------|--------------------------|---|------------|---|-------------|--|
| 70300260    | TEMP PVT MK LINE 12   | FOOT            | 2,627.000                |   |            |   |             |  |
| * 70300280  | TEMP PVT MK LINE 24   | FOOT            | 565.000                  |   |            |   |             |  |
| 70301000    | WORK ZONE PAVT MK REM | SQ FT           | 2,006.000                |   |            |   |             |  |
| 78003130    | PREF PL PM TB LINE 6  | FOOT            | 5,480.000                |   |            |   |             |  |
| * 78005100  | EPOXY PVT MK LTR-SYM  | SQ FT           | 1,569.000                |   |            |   |             |  |
| * 78005110  | EPOXY PVT MK LINE 4   | FOOT            | 74,332.000               |   |            |   |             |  |
| * 78005140  | EPOXY PVT MK LINE 8   | FOOT            | 12,687.000               |   |            |   |             |  |
| * 78005150  | EPOXY PVT MK LINE 12  | FOOT            | 2,523.000                |   |            |   |             |  |
| * 78005180  | EPOXY PVT MK LINE 24  | FOOT            | 565.000                  |   |            |   |             |  |
| * 78100100  | RAISED REFL PAVT MKR  | EACH            | 712.000                  |   |            |   |             |  |
| 78200405    | GUARDRAIL MARKERS     | EACH            | 46.000                   |   |            |   |             |  |
| 78201000    | TERMINAL MARKER - DA  | EACH            | 6.000                    |   |            |   |             |  |
| * 78300200  | RAISED REF PVT MK REM | EACH            | 642.000                  |   |            |   |             |  |
| * 88600100  | DET LOOP T1           | FOOT            | 1,480.000                |   |            |   |             |  |
|             |                       |                 | * REVISED : JUNE 1, 2007 |   |            |   |             |  |