

SUMMARY OF QUANTITIES

P. & S. SHEET NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	35RS-5,3GRS-8	TAZEWELL	90	4
STAL	TO STAL			
FED. ROAD DIST. NO. 5	ILLINOIS	FED. AID PROJECT		
*6717 (BUS 24) & 6713 (IL 8)				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		1000 100% STATE	BRIDGE X241-2A 100% STATE	CITY 1000-1A 100%	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	114	114			
28001000	AGGREGATE (EROSION CONTROL)	TON	87	87			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	21	21			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	13	13			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	62.0 65.0	61.3 64.3		0.7	
40600300	AGGREGATE (PRIME COAT)	TON	329 347	325 343		4	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2410 2537	2410 2537			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3084 2932	2940 2788		144	
40600990	TEMPORARY RAMP	SQ YD	521 602	408 489		113	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2542	2542			
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8842 9393	8689 9240		153	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	318	318			
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	20,317 23406	20,317 23406			
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	15734	15734			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	88,820 92522	87,150 90852		1670	
44000158	HOT - MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	8390	8390			
44201369	CLASS C PATCHES, TYPE III, 11 INCH	SQ YD	47	47			
44201371	CLASS C PATCHES, TYPE IV, 11 INCH	SQ YD	69 70	69 70			
44201389	CLASS C PATCHES, TYPE II, 13 INCH	SQ YD	26 78	26 78			

⚠ REVISÉ 6/1/07