

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
35RS-5,36RS-8	TAZEWELL		90	40
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*6717 (BUS 24) & 6713 (IL 8)				

PATCHING SCHEDULE

LOCATION	CLASS C, TYPE III, 11"	CLASS C, TYPE IV, 11"	CLASS C, TYPE II, 13"	CLASS C, TYPE III, 13"	CLASS C, TYPE IV, 13"	CLASS D, TYPE II, 13"	CLASS D, TYPE III, 13"	CLASS D, TYPE IV, 15"	CLASS D, TYPE II, 17"	CLASS D, TYPE III, 17"	CLASS D, TYPE IV, 17"	TIE BARS 3/4"
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	EACH
RAMPS								40.0				
BUS 24 STA. 426+29.46 - 461+30									22.4			
BUS 24 STA. 461+30 - 495+11.58		44.4		16.0	105.7		45.3					9.0
IL 8 STA. 191+00 - 258+65			52 *						1095	159	615	
IL 8 STA. 258+65 - 293+65	16.0			90.6								
IL 8 Sta. 293+65 - 322+28	16.0		26		32.0	10.0						
SUBTOTALS	32.0	44.4	78	106.6	137.7	10.0	45.3	40.0	1117			9.0
SPRING BREAKUP	15.0	25.0		15.0	25.0	5.0	15.0	25.0				
TOTALS	47	69	78	122	163	15	60	65	1117	159	615	9

* @ CONCRETE TURN LANE

RESURFACING - BUS U.S. ROUTE 24 (SHOULDERS)

	AREA	HMA SURF REMOVAL BT JT	HMA SURF REMOVAL 3/4"	HMA SURF REMOVAL 1-1/2"	BITUMINOUS MATERIALS (PRIME)	AGGREGATE (PRIME)	HMA SURF CSE, MIX C, N50, 1.5"
	SQ FT	SQ YD	SQ YD	SQ YD	TON	TON	TON
WEST BOUND (INSIDE)							
449+26.41 - 461+65.95	4958.2		550.9		0.22	1.1	46.3
462+73.28 - 475+13.31	4960.1		551.1		0.22	1.1	46.3
475+13.31 - 475+58.91	182.4			20.3	0.01	0.0	1.7
475+58.91 - 475+73.91	60.0	6.7			0.00	0.0	0.6
490+63.10 - 490+78.10	60.0	6.7			0.00	0.0	0.6
490+78.10 - 494+65.68	1579.6			175.5	0.07	0.4	14.7
WEST BOUND (OUTSIDE)							
449+26.41 - 450+30	828.7		92.1		0.04	0.2	7.7
450+30 - 461+13.73	10866.9		1207.4		0.48	2.4	101.4
463+17.34 - 475+13.31	10039.7		1115.5		0.45	2.2	93.7
475+13.31 - 475+28.31	150.0	16.7			0.01	0.0	1.4
483+58.84 - 483+73.84	150.0	16.7			0	0.0	1.4
483+73.84 - 494+65.68	10095.5			1121.7	0.45	2.2	94.2
TOTALS		47	3517	1317	2	9.6	410

AGGREGATE FOR TEMPORARY ACCESS

LOCATION	TON
IL ROUTE 8	
RT. STA. 259+83	2.1
LT. STA. 265+00	1.0
RT. STA. 278+90	2.4
RT. STA. 288+00	1.0
RT. STA. 290+00	1.0
RT. STA. 296+40	1.0
RT. STA. 301+00	1.0
LT. STA. 305+69	1.0
RT. STA. 310+65	1.0
RT. STA. 320+70	1.2
TOTAL	13

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. DATE
HORIZ.

DRAWN BY
CHECKED BY