

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(44,45)RS-5, (46-1)RS-7, (45-RB, RB-2, BR)	PEORIA		5
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES					80 % FEDERAL FUNDING / 20 % STATE FUNDING			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN				
				INTERSTATE ROADWAY	ROADWAY / STRUCTURES 072-0008	BRIDGE S.N. 072-0136	BRIDGE S.N. 072-0010	
				1000	SFTY - 2A	X081 - 2A	SFTY - 2A	
44213200	SAW CUTS	FOOT	16,053	16,053				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	567	567				
48203100	HOT-MIX ASPHALT SHOULDERS	TON	12,069	12,069				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1			1		
50102400	CONCRETE REMOVAL	CU YD	41.1			5.5	35.6	
50300225	CONCRETE STRUCTURES	CU YD	6.0			6.0		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	35.6				35.6	
50300260	BRIDGE DECK GROOVING	SQ YD	542			542		
50301200	CONCRETE WEARING SURFACE	SQ YD	51				51	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	5,117			5,117		
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	1,556				1,556	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	204				204	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	11,740			8,310	3,430	
50800515	BAR SPLICERS	EACH	138			138		
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	201				201	
* 50901050	STEEL BRIDGE RAIL, TYPE SM	FOOT	244			244		
51500100	NAME PLATES	EACH	1			1		

* SPECIALTY ITEM

SUMMARY OF QUANTITIES