

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(44-45)RS-5, (46-1)RS-7, (45-0)RB-2,(BR)	PEORIA	82	22
FED. ROAD DIST. NO. - ILLINOIS			FED. AID PROJECT	

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	HOT-MIX ASPHALT SURFACE REM. BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE REM. 2.25 IN	HOT-MIX ASPHALT SURFACE REM. 0.5 IN	POLYMERIZED BITUMINOUS MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	POLYMERIZED LEVEL BINDER SUPER, IL-4.75 (METHOD), N50	POLYMERIZED HMA SURFACE CSE MIX "D", N70	HOT-MIX ASPHALT SHOULDERS			
												LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	SQ YD	TON	SQ YD	TON
STA. 475 + 17 TO 492 + 38	8.00	1665.00	1480.00					0.59	2.96			1480.00	186.48		
STA. 492 + 38 TO 496 + 26	8.00	388.00	344.89					0.14	0.69			344.89	43.46		
BRIDGE OMISSION															
STA. 497 + 51 TO 505 + 82	8.00	831.00	738.67					0.30	1.48			738.67	93.07		
STA. 505 + 82 TO 519 + 45	6-5	1363.00	707.23			707.23		0.28	1.41			707.23	89.11		
STA. 519 + 45 TO 521 + 41	5.00	196.00	108.89			108.89		0.04	0.22			108.89	13.72		
STA. 521 + 41 TO 526 + 41	6-5	500.00	160.44			160.44		0.06	0.32			160.44	20.22		
STA. 526 + 41 TO 535 + 53	6.00	912.00	608.00			608.00		0.24	1.22			608.00	76.61		
STA. 535 + 53 TO 538 + 71	8.00	318.45	283.07					0.11	0.57			283.07	35.67		
STA. 538 + 70 TO 559 + 00	8.00	2030.48	1804.87					0.72	3.61			1804.87	227.41		
STA. 559 + 00 TO 565 + 63	6-2	606.00	195.15			195.15		0.08	0.39			195.15	24.59		
STA. 565 + 63 TO 572 + 25	6-4	629.00	285.96			285.96		0.11	0.57			285.96	36.03		
STA. 572 + 25 TO 579 + 26	6-2	701.00	458.48			458.48		0.18	0.92			458.48	57.77		
STA. 579 + 26 TO 589 + 95	2.00	928.07	206.24			206.24		0.08	0.41			206.24	25.99		
STA. 589 + 95 TO 590 + 94	0.00	99.00													
STA. 590 + 94 TO 596 + 94	0.00	600.00													
STA. 596 + 94 TO 605 + 85	0.00	890.85													
STA. 605 + 89 TO 607 + 38	0.00	149.40													
TURNLANES															
CAMERON LANE EB LT			806.90			806.90		0.32	1.61	33.89	67.78				
FACTORY ROAD WB LT			3286.72			3286.72		1.31	6.57	138.04	276.08				
WALNUT ST. EB LT			3946.25			3946.25		1.58	7.89	165.74	331.49				
FACTORY ROAD EB MERGE LN			1267.56			1267.56		0.51	2.54	53.24	106.48				
FACTORY ROAD EB RT			314.00			314.00		0.13	0.63	13.19	26.38				
REED CITY ROAD EB LT			550.00				550.00	0.22	1.10	23.10	46.20				
TERMINAL ROAD EB RT			624.67			624.67		0.25	1.25	26.24	52.47				
TERMINAL ROAD EB MERGE LN			1956.00			1956.00		0.78	3.91	82.15	164.30				
TERMINAL ROAD WB LT			2627.47			2627.47		1.05	5.25	110.35	220.71				
TERMINAL ROAD WB MERGE LN			2263.44			2263.44		0.91	4.53	95.06	190.13				
JACKSON ST WB LT			793.33			793.33		0.32	1.59	33.32	66.64				
JACKSON ST EB LT			750.83			750.83		0.30	1.50	31.54	63.07				
WASHINGTON ST WB LT			1390.00			1390.00		0.56	2.78	58.38	116.76				
PEARL STREET EB LT			793.30			793.30		0.32	1.59	33.32	66.64				
SUB-TOTAL						23,551	550	11.5	57.5	898	1,795	930			

SCHEDULE OF QUANTITIES