

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	QUANTITY	UNITS	PRICE
F.A.P. 317	(48B)1	PEORIA	29	3
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

D-94-062-05

COMBINATION CURB AND GUTTER REMOVAL	
LOCATION	FOOT
EB U.S. 24 RIGHT STA. 185+29 TO STA. 186+07	79
TOTAL	79

BITUMINOUS CONCRETE SHOULDER REMOVAL	
LOCATION	SO YD
EB U.S. 24 RIGHT STA. 185+76 TO STA. 185+90	3
TOTAL	3

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	
LOCATION	FOOT
EB U.S. 24 RIGHT STA. 185+29 TO STA. 186+07	79
TOTAL	79

PORTLAND CEMENT CONCRETE SHOULDERS 6"	
LOCATION	SO YD
EB U.S. 24 RIGHT STA. 185+52 TO STA. 186+05	15
TOTAL	15

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
E.B.	
STA. 173+70 TO STA. 176+00	19
STA. 183+75 TO STA. 187+50	125
STA. 182+50 TO STA. 187+50	167
STA. 187+50 TO STA. 187+60	3
W.B.	
STA. 183+15 TO STA. 186+14	25
STA. 183+15 TO STA. 186+14	100
STA. 187+50 TO STA. 189+90	80
STA. 187+50 TO STA. 191+50	133
TOTAL	652

TRAFFIC CONTROL AND PROTECTION	
LOCATION	L SUM
STA. 173+70 TO STA. 201+50	1
TOTAL	1

EPOXY PAVEMENT MARKING - LINE 4"	
LOCATION	FOOT
SOLID WHITE	
E.B.	
STA. 173+70 TO STA. 181+20	750
STA. 182+50 TO STA. 191+50	900
W.B.	
STA. 183+15 TO STA. 191+50	835
SOLID YELLOW	
E.B.	
STA. 173+70 TO STA. 181+20	750
STA. 182+50 TO STA. 191+50	900
W.B.	
STA. 183+15 TO STA. 191+50	835
TOTAL	4970

EPOXY PAVEMENT MARKING - LINE 6"	
LOCATION	FOOT
SKIP-WHITE	
E.B.	
STA. 173+70 TO STA. 181+20	750
STA. 182+50 TO STA. 191+50	450
W.B.	
STA. 183+15 TO STA. 191+50	418
TOTAL	1618

EPOXY PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
SOLID WHITE	
E.B.	
STA. 178+00 TO STA. 180+40	240
W.B.	
STA. 183+15 TO STA. 184+15	200
TOTAL	440

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	
LOCATION	TON
E.B. STA. 185+29 TO STA. 186+29	38
W.B. STA. 185+29 TO STA. 186+29	34
STA. 186+29 TO STA. 187+40 (BRIDGE)	88
TOTAL	160

HOT-MIX ASPHALT SURFACE REMOVAL, 1"	
LOCATION	SO. YD.
E.B. STA. 185+29 TO STA. 186+29	446
W.B. STA. 185+29 TO STA. 186+29	408
TOTAL	854

STAGING PAY ITEMS (Sheets 5-10)						
	TEMP CONC BARRIER	REL TEMP CONC BARRIER	IMP ATTN TEMP NRD TL2	IMP ATTN REL NRD TL2	PAVT MARK TAPE T3 4	PAVT MARK TAPE T3 8
	FOOT	FOOT	EACH	EACH	FOOT	FOOT
STAGE 1						
Sheet 5	423		1		2858	200
Sheet 6	164		1		2001	
STAGE 2						
Sheet 7	275	425		1	1514	
Sheet 8	14	160		1	1102	301
STAGE 3						
Sheet 9		566		1	1959	
Sheet 10		306		1	1665	
TOTAL	876	1457	2	4	11099	501

DESIGNED - JRG
CHECKED - JFS
DRAWN - ACJ
CHECKED - JRG/JFS

SCHEDULE OF QUANTITIES
F.A.P. 317 (U.S. RTE. 24)
STRUCTURE 072-0134
PEORIA COUNTY, ILLINOIS
STATION 187+10.02