

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	(102-2.3)RS	WOODFORD	15	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

* FAP 412 ROUTE 1-39/US51

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	1000 CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		90% FED. 10% STATE					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	68	68					
40600300	AGGREGATE (PRIME COAT)	TON	638	638					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1413	1413					
40600990	TEMPORARY RAMP	SQ YD	236	236					
40603080	HOT - MIX ASPHALT BINDER COURSE, IL - 19.0, N50	TON	11916	11916					
40603245	POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL - 19.0, N105	TON	15837	15837					
40603310	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	7432	7432					
40603335	HOT MIX - ASPHALT SURFACE COURSE, MIX "D", N50	TON	511	511					
40603575	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	10558	10558					
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	409	409					
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	229	229					
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	1355	1355					
44213000	PATCHING REINFORCEMENT	SQ YD	1993	1993					
44213200	SAW CUTS	FOOT	9096	9096					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6756	6756					
64200105	SHOULDER RUMBLE STRIP	FOOT	91020	91020					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<p align="center">SUMMARY OF QUANTITIES</p> <p>SCALE: VERT. _____ HORIZ. _____</p> <p>DATE _____ DRAWN BY _____ CHECKED BY _____</p>	

PLOT DATE = 04/18/88
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#