F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	*	MCDONOUGH		4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D4 CULVERT REPAIR 2007 68602

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	X028-2A		
67100100	MOBILIZATION	L SUM	1.0	1.0		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0	1.0		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1.0	1.0		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0		
70103815	TRAFFIC CONTROL SURVELLIANCE	CAL DA	2.0	2.0		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0	1.0		
70106700	TEMPORARY RUMBLE STRIP	EACH	6.0	6.0		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	384.0	384.0		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1964.0	1964.0		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	52.0	52.0		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	366.1	366.1		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	318.0	318.0		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	318.0	318.0		
* 78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	1410.0	1410.0		
* 78005130	EPOXY PAVEMENT MARKING-LINE 6"	FOOT	180.0	180.0		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	X028-2A		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	20.0	20.0		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0	4.0		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	489.0	489.0		
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	106.4	106.4		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	65.0	65.0		
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2.0	2.0		
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2.0	2.0		
Z0054500	ROCK FILL	TON	40.6	40.6		

* SPECIALTY ITEM