

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
701	D4 DRAIN IMP	TAZEWELL	27	3
STA.	TO STA.			
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QTY.	ROADWAY MAIN
20200100	EARTH EXCAVATION	CU YD	1261.0	1261.0
20400800	FURNISHED EXCAVATION	CU YD	449	449
20800150	TRENCH BACKFILL	CU YD	21.2	21.2
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	674	674
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5208	5208
25000312	SEEDING CLASS 4A	ACRE	1.08	1.08
25000350	SEEDING CLASS 7	ACRE	1.15	1.15
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	200	200
25000500	PHOSPHOUS FERTILIZER NUTRIENT	POUND	200	200
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	200	200
28000400	PERIMETER EROSION BARRIER	FOOT	1854	1854
28000500	INLET AND PIPE PROTECTION	EACH	1.0	1.0
44201789	CLASS D PATCHES, TYPE II, 12 IN.	SQ YD	12.3	12.3
54200445	PIPE CULVERT TYPE 1 RCCP 30"	FOOT	44.0	44.0

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QTY.	ROADWAY MAIN
54223459	REMOVE & RELAY PIPE CULVERT 24"	FOOT	40.0	40.0
54213675	PRECAST ^{REINFORCED} CONCRETE/FLARED END SECTION 30"	EACH	2.0	2.0
60102105	PIPE DRAINS 15" (SPECIAL)	FOOT	200	200
67100100	MOBILIZATION	L. SUM	1.0	1.0
70100460	TRAFFIC CONTROL & PROTECTION 701201	L. SUM	1.0	1.0
70100480	TRAFFIC CONTROL & PROTECTION 701306	L. SUM	1.0	1.0
X0323865	FILL EXISTING DRAINAGE STRUCTURE, NO. 1	EACH	1.0	1.0

PLOT DATE = 5/2/2007
 FILE NAME = S:\GEN\DRAWING\STD&PLNS\Squad11A\68643\CoverSht thru Schedule of Qty.dgn
 PLOT SCALE = 42.4074' / IN.
 USER NAME = brucebm

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE _____ CHECKED BY _____