

F.A.P. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	PEORIA	22	3
STA. 215+18.77 TO STA. 246+46.02			
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT			
• 04 JOINT REPAIR 2007-3			

SUMMARY OF QUANTITIES

100% STATE SAFETY - 2A
URBAN

CODE NO.	ITEM	UNIT	PEORIA	TAZEWELL	TOTAL
42001300	PROTECTIVE COAT	SQYD	80	120	200
50102400	CONCRETE REMOVAL	CUYD	22.6	33.9	56.5
50157300	PROTECTIVE SHIELD	SQYD	187	233	420
50300255	CONCRETE SUPERSTRUCTURE	CUYD	22.6	33.9	56.5
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,380	6,570	10,950
50800515	BAR SPLICERS	EACH	62	94	156
67100100	MOBILIZATION	LSUM	0.4	0.6	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	LSUM	0.4	0.6	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	LSUM	0	1	1
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	0.4	0.6	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	0	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	8	13
X7015105	OPERATE CHANGEABLE MESSAGE SIGN	EACH	0	2	2

PLOT DATE *DATE*
PLOT NAME *FILE*
PLOT SCALE *SCALE*
PLOT REFERENCE *REF*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY CEJ
 HORIZ. CHECKED BY
 DATE 07-07-2006