CONTRACT NO. 70626

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	57(RA-L)	MCLEAN	12	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

70626

SUMMARY OF QUANTITIES

LOCATION OF WORK: Interstate 55
Funks Grove Rest Area

McLean County
Highway Lighting
100% State

CONSTRUCTION TYPE CODE: Y030-1E

CODE NO	ITEM	UNIT	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1.0
70103710	TRAFFIC CONTROL FOR RAMPS	L SUM	1.0
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	197.0
81603070	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1,990.0
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,833.0
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	1.0
82105400	LUMINAIRE, SODIUM VAPOR, HIGH MAST, MULTI-MOUNT, 400 WATT	EACH	16.0
83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT	EACH	1.0
83501500	LIGHT TOWER, 90 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 8	EACH	2.0
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	7.0
83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	35.0
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	4.0
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	2.0
84200700	LIGHTING FOUNDATION REMOVAL	EACH	2.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE = 4/5/2007
FILE NAME = u:\projects\d514006 ill\plan sheets.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = bieggerd