CONTRACT NO. 70628

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	**	153	9
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D5 SAFETY IMPROVEMENT 2007-2
** CHAMPAIGN, COLES, & DOUGLAS

SUMMARY OF QUANTITIES

SHEET 1 OF 2

100% STATE

	LOCATION OF WORK:			FAI 57 I - 57 RURAL COLES COUNTY STA 1382+78.35 TO 1386+91.00	FAI 57 I - 57 RURAL DOUGLAS COUNTY STA 1386+91.00 TO STA 848+50.05	FAI 57 I - 57 RURAL CHAMPAIGN COUNTY STA 848+50.05 TO STA 244+06.15 STA 680+87.80 TO STA 1258+10.00 STA 1292+95.00 TO STA 1649+18.87	FAI 57 I -57 URBAN CHAMPAIGN COUNTY STA 244+06.15 TO STA 680+87.80 STA 1258+10.00 TO STA 1292+95.00	FAI 57 I-57 RURAL CHAMPAIGN SN 010-0200 STA 940+86.71
	FUNDING BREAKOUT:			90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	MOTORIST CAUSED HIGHWAY DAMAGE
	CONSTRUCTION TYPE CODE:			SFTY-3J	SFTY-3J	SFTY-3J	SFTY-3J	SFTY-3J
	CODE NO	ITEM	UNIT	TOTAL QUANTITY				
	60226242	RESTRICTED DEPTH MANHOLES, 7'-DIAMETER, TYPE 8 GRATE	EACH	4.0	0.0	0.0	3.0	1.0	0.0
	20400800	FURNISHED EXCAVATION	CU YD	5689.0	64.0	1448.0	3026.0	1151.0	0.0
*	25000210	SEEDING, CLASS 2A	ACRE	8.1	0.30	3.2	3.6	1.0	0.0
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	727.5	26.1	288.9	320.9	91.6	0.0
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	727.5	26.1	288.9	320.9	91.6	0.0
*	25000600	POTASSIUM FERTILIZER NURTIENT	POUND	727.5	26.1	288.9	320.9	91.6	0.0
*	25100115	MULCH, METHOD 2	ACRE	8.1	0.30	3.2	3.6	1.0	0.0
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	804.5	29.0	317.1	356.6	101.8	0.0
	28000300	TEMPORARY DITCH CHECKS	EACH	41.0	2.0	20.0	16.0	3.0	0.0
	28000500	INLET AND PIPE PROTECTION	EACH	12.0	1.0	4.0	6.0	1.0	0.0
	35200600	EARTH EXCAVATION	CU YD	181.0	22.2	69.8	89.0	0.0	0.0
	50102400	CONCRETE REMOVAL	CU YD	0.4	0.0	0.0	0.0	0.0	0.4
	50104400	CONCRETE HEADWALL REMOVAL	EACH	2.0	0.0	2.0	0.0	0.0	0.0
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	0.4	0.0	0.0	0.0	0.0	0.4
	50800205	REINFORCED BARS, EPOXY COATED	POUND	2,471.1	0.0	1,147.4	1106.7	187.0	30.0
	54213693	PRECAST REINFORCED CONCRETE FLARED END SECTION 48"	EACH	2.0	0.0	2.0	0.0	0.0	0.0
	54244405	FLUSH INLET BOX MEDIAN, STANDARD 542546	EACH	1.0	0.0	1.0	0.0	0.0	0.0
	54246205	INLET BOX, STANDARD 542526	EACH	3.0	0.0	0.0	2.0	1.0	0.0
	54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	2.0	0.0	2.0	0.0	0.0	0.0
	54248510	CONCRETE COLLAR	CU YD	1.8	0.0	0.0	1.8	0.0	0.0
	542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	154.0	0.0	154.0	0.0	0.0	0.0
	542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	417.0	0.0	0.0	314.0	103.0	0.0
	60107600	PIPE UNDERDRAINS 4"	FOOT	75.0	0.0	20.0	44.0	11.0	0.0
	60226270	RESTRICTED DEPTH MANHOLES, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2.0	0.0	1.0	1.0	0.0	0.0
	60500090	REMOVE INLETS TO MAINTAIN FLOW	EACH	7.0	0.0	1.0	5.0	1.0	0.0

*SPECIALTY ITEM

PLOT DATE = 3/30/2007
FILE NAME = c:\projects\d514406 lv81\70628allsheets.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = piersonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I. ROUTE 57 (I-57)
SECTION D5 SAFETY IMPROVEMENT 2007-2
CHAMPAIGN, COLES, & DOUGLAS COUNTIES
Sheet 1 of 2

SCALE: NOT TO SCALE — DRAWN BY: B.B.P.
DATE: 03/24/07 — CHECKED BY: M.L.B.