

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	••	153	20

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

• D5 SAFETY IMPROVEMENT 2007-2
•• CHAMPAIGN, COLES, & DOUGLAS

010-0198 & 010-0199, Con't.

63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION TO	STATION		EACH
117+40.26	117+85.91	RT	1.0
117+40.26	117+85.91	MED RT	1.0
119+14.10	119+59.75	LT	1.0
119+14.10	119+59.75	MED LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
114+77.76	RT	1.0
114+15.26	MED RT	1.0
122+22.25	LT	1.0
122+84.75	MED LT	1.0

010-0145 (THE GUARDRAIL RUNS ACROSS 010-8300 ON THE LT.)

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
167+52.13	170+02.13	RT	250.00
170+67.90	174+80.40	LT	412.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
166+70.93	167+20.93	RT	1.0
175+86.55	176+36.55	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
167+20.93	169+33.43	RT	212.50
171+36.55	173+61.55	LT	225.00
174+36.55	175+86.55	LT	150.00

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION TO	STATION		LENGTH (FT)
173+61.55	173+86.55	LT	25.00
174+11.55	174+36.55	LT	25.00

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

STATION TO	STATION		LENGTH (FT)
173+86.55	174+11.55	LT	25.00

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
169+33.43	169+90.08	RT	1.0
170+79.90	171+36.55	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
166+70.93	RT	1.0
176+36.55	LT	1.0

010-8300 & 010-8301

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
172+86.25	174+36.25	RT	150.00
172+86.25	174+36.25	MED RT	150.00
173+93.75	175+43.75	MED LT	150.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
172+52.23	173+02.23	RT	1.0
171+29.55	171+79.55	MED RT	1.0
177+31.55	177+81.55	MED LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
173+02.23	174+14.73	RT	112.50
171+79.55	174+04.55	MED RT	225.00
174+56.55	177+31.55	MED LT	275.00

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION TO	STATION		LENGTH (FT)
174+14.73	174+39.73	RT	25.00
174+04.55	174+29.55	MED RT	25.00
174+31.55	174+56.55	MED LT	25.00

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

STATION TO	STATION		LENGTH (FT)
174+39.73	174+64.73	RT	25.00
174+29.55	174+54.55	MED RT	25.00
174+06.55	174+31.55	MED LT	25.00

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
174+64.73	174+79.00	RT	1.0
174+54.55	174+68.82	MED RT	1.0
173+92.28	174+06.55	MED LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
172+52.23	RT	1.0
171+29.55	MED RT	1.0
177+31.55	MED LT	1.0

010-0181

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
256+51.80	258+89.30	RT	237.50
258+72.30	261+22.30	LT	250.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
255+66.65	256+16.65	RT	1.0
261+44.95	261+94.95	LT	1.0

010-0181, Con't.

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
256+16.65	258+29.15	RT	212.50
259+32.45	261+44.95	LT	212.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
258+29.15	258+85.80	RT	1.0
258+75.80	259+32.45	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
255+66.65	RT	1.0
261+94.95	LT	1.0

010-8008

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
358+52.20	361+66.47	RT	314.27
360+60.83	363+75.10	LT	314.27

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
358+52.20	359+02.20	RT	1.0
363+25.10	363+75.10	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
359+02.20	361+52.20	RT	250.00
360+75.10	363+25.10	LT	250.00

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
361+52.20	361+66.47	RT	1.0
360+60.83	360+75.10	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
358+52.20	RT	1.0
363+75.10	LT	1.0

PLOT DATE = 3/30/2007
FILE NAME = c:\p\projects\d514406\108\70628\sheet7.dgn
PLOT SCALE = 42.3529 / 1 IN.
USER NAME = pfer-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
F.A.I. ROUTE 57 (I-57)
SECTION D5 SAFETY IMPROVEMENT 2007-2
CHAMPAIGN, COLES, & DOUGLAS COUNTIES
Page 7 of 19

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
DATE: 03/23/07 CHECKED BY: M.L.B.