

# GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	••	153	28
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D5 SAFETY IMPROVEMENT 2007-2 •• CHAMPAIGN, COLES, & DOUGLAS				

010-0193

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)	
918+02.50		920+52.50	250.00	RT
919+52.50		922+02.50	250.00	LT

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH	
917+15.00		917+65.00	1.0	RT
922+40.00		922+90.00	1.0	LT

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)	
917+65.00		919+90.00	225.00	RT
920+15.00		922+40.00	225.00	LT

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION	TO	STATION	LENGTH (FT)	
919+90.00		920+15.00	25.00	RT
919+90.00		920+15.00	25.00	LT

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

STATION	TO	STATION	LENGTH (FT)	
920+15.00		920+40.00	25.00	RT
919+65.00		919+90.00	25.00	LT

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH	
920+40.00		920+54.27	1.0	RT
919+50.73		919+65.00	1.0	LT

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH	
917+15.00	1.0	RT
922+90.00	1.0	LT

010-2002

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)	
949+96.00		952+33.50	237.50	RT
953+62.50		956+00.00	237.50	LT

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH	
949+42.24		949+92.24	1.0	RT
955+82.76		956+32.76	1.0	LT

010-2002, Con't.

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)	
949+92.24		952+54.74	262.50	RT
953+45.26		955+82.76	237.50	LT

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH	
952+54.74		952+69.01	1.0	RT
953+30.99		953+45.26	1.0	LT

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH	
949+42.24	1.0	RT
956+32.76	1.0	LT

010-0156

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)	
1014+72.54		1016+85.60	213.06	RT
1016+72.50		1018+85.00	212.50	LT

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH	
1013+65.57		1014+15.57	1.0	RT
1019+41.87		1019+91.87	1.0	LT

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)	
1014+15.57		1016+28.07	212.50	RT
1017+29.37		1019+41.87	212.50	LT

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH	
1016+28.07		1016+84.72	1.0	RT
1016+72.72		1017+29.37	1.0	LT

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH	
1013+65.57	1.0	RT
1019+91.87	1.0	LT

010-8033

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)	
1018+95.43		1021+33.76	238.33	RT
1021+26.80		1023+65.84	239.04	LT

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH	
1018+81.50		1019+31.50	1.0	RT
1022+79.50		1023+29.50	1.0	LT

010-8033, Con't.

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)	
1019+31.50		1021+19.00	187.50	RT
1020+92.00		1022+79.50	187.50	LT

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH	
1021+19.00		1021+33.27	1.0	RT
1020+77.73		1020+92.00	1.0	LT

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH	
1018+81.50	1.0	RT
1021+42.00	1.0	LT

PLOT DATE = 3/30/2007  
 FILE NAME = c:\projects\010-0193\010-0193.dwg  
 PLOT SCALE = 42.3529 / IN.  
 USER NAME = pfer-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**GUARDRAIL SCHEDULES**  
 F.A.I. ROUTE 57 (I-57)  
 SECTION D5 SAFETY IMPROVEMENT 2007-2  
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES  
 Page 15 of 19  
 SCALE: NOT TO SCALE  
 DATE: 03/23/07  
 DRAWN BY: B.B.P.  
 CHECKED BY: M.L.B.