

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	.	..	153	30
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D5 SAFETY IMPROVEMENT 2007-2 •• CHAMPAIGN, COLES, & DOUGLAS				

010-0164

63200310 GUARDRAIL REMOVAL

STATION TO	STATION	LENGTH (FT)
1233+36.69	1235+36.70	RT 200.01
1235+35.83	1237+37.92	LT 202.09

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION	EACH
1232+32.18	1232+82.18	RT 1.0
1238+08.48	1238+58.48	LT 1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION	LENGTH (FT)
1232+82.18	1234+94.68	RT 212.50
1235+95.98	1238+08.48	LT 212.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION	EACH
1234+94.68	1235+51.33	RT 1.0
1235+39.33	1235+95.98	LT 1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1232+32.18	RT 1.0
1238+58.48	LT 1.0

CHAMPAIGN COUNTY: URBAN

010-0012 & 010-0013

63200310 GUARDRAIL REMOVAL

STATION TO	STATION	LENGTH (FT)
1273+03.08	1274+54.98	RT 151.90
1273+03.08	1274+54.98	MED RT 151.90
1276+41.02	1277+92.92	LT 151.90
1276+41.02	1277+92.92	MED LT 151.90

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION	EACH
1271+46.83	1271+96.83	RT 1.0
1270+46.83	1270+96.83	MED RT 1.0
1278+99.37	1279+49.37	LT 1.0
1279+99.37	1280+49.37	MED LT 1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION	LENGTH (FT)
1271+96.83	1274+09.33	RT 212.50
1270+96.83	1274+09.33	MED RT 312.50
1276+86.87	1278+99.37	LT 212.50
1276+86.87	1279+99.37	MED LT 312.50

010-0012 & 010-0013, Con't.

63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION TO	STATION	EACH
1274+09.33	1274+54.98	RT 1.0
1274+09.33	1274+54.98	MED RT 1.0
1276+41.02	1276+86.87	LT 1.0
1276+41.02	1276+86.87	MED LT 1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1271+46.83	RT 1.0
1270+46.83	MED RT 1.0
1279+49.37	LT 1.0
1280+49.37	MED LT 1.0

CHAMPAIGN COUNTY: RURAL

010-0191 & 010-0192

63200310 GUARDRAIL REMOVAL

STATION TO	STATION	LENGTH (FT)
1311+28.13	1315+15.63	RT 387.50
1312+90.86	1315+03.36	MED RT 212.50
1316+72.87	1328+97.87	RT 1225.00
1303+76.44	1314+76.44	LT 1100.00
1316+43.33	1318+43.33	MED LT 200.00
1316+31.06	1328+68.56	LT 1237.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION	EACH
1311+19.98	1311+69.98	RT 1.0
1310+95.48	1311+45.48	MED RT 1.0
1328+26.71	1328+76.71	LT 1.0
1320+01.48	1320+51.48	MED LT 1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION	LENGTH (FT)
1311+69.98	1314+69.98	RT 300.00
1311+45.48	1314+57.98	MED RT 312.50
1317+18.52	1328+93.52	RT 1175.00
1303+80.79	1314+30.79	LT 1050.00
1316+88.98	1320+01.48	MED LT 312.50
1316+76.71	1328+26.71	LT 1150.00

010-0191 & 010-0192, Con't.

63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION TO	STATION	EACH
1314+69.98	1315+15.63	RT 1.0
1314+57.98	1315+03.63	MED RT 1.0
1316+72.87	1317+18.52	RT 1.0
1314+30.79	1314+76.44	LT 1.0
1316+43.33	1316+88.98	MED LT 1.0
1316+31.06	1316+76.71	LT 1.0

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION	EACH
1328+93.52	1329+07.79	RT 1.0
1303+66.52	1303+80.79	LT 1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1311+19.98	RT 1.0
1310+95.48	MED RT 1.0
1328+76.71	LT 1.0
1320+51.48	MED LT 1.0

010-0163

63200310 GUARDRAIL REMOVAL

STATION TO	STATION	LENGTH (FT)
1343+67.67	1347+30.17	RT 362.50
1346+82.67	1350+32.67	LT 350.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION	EACH
1344+35.24	1344+85.24	RT 1.0
1349+10.10	1349+60.10	LT 1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION	LENGTH (FT)
1344+85.24	1346+72.74	RT 187.50
1347+22.60	1349+10.10	LT 187.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION	EACH
1346+72.74	1347+29.39	RT 1.0
1346+65.95	1347+22.60	LT 1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1344+35.24	RT 1.0
1349+60.10	LT 1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\p\projects\d514406\108\70628\sheet30.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
 Page 17 of 19

SCALE: NOT TO SCALE
 DATE: 03/23/07
 DRAWN BY: B.B.P.
 CHECKED BY: M.L.B.