

SCHEDULE OF QUANTITIES

SHEET 12 of 13

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	.	..	153	44
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- D5 SAFETY IMPROVEMENT 2007-2
- CHAMPAIGN, COLES, & DOUGLAS

54213693 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"

STATION	TYPE	EACH
DOUGLAS COUNTY: RURAL		
258+80.00 RT	PIPE CULVERT 48"	1.0
258+80.00 LT	PIPE CULVERT 48"	1.0
TOTAL =		2.0

54244405 FLUSH INLET BOX MEDIAN STANDARD 542546

STATION	DESCRIPTION	EACH
DOUGLAS COUNTY: RURAL		
150+00.00	S. N. 021-0041	1.0
TOTAL =		1.0

54246205 INLET BOX STANDARD 542526

STATION	DESCRIPTION	EACH
CHAMPAIGN COUNTY: RURAL		
257+00.00	010-0181	1.0
260+50.00	010-0181	1.0
CHAMPAIGN COUNTY: URBAN		
352+00.00	010-0176	1.0
TOTAL =		3.0

54247190 GRATING FOR CONCRETE FLARED END SECTION 48"

STATION	TYPE	EACH
DOUGLAS COUNTY: RURAL		
258+80.00 RT	PIPE CULVERT 48"	1.0
258+80.00 LT	PIPE CULVERT 48"	1.0
TOTAL =		2.0

54248510 CONCRETE COLLAR

STATION	DESCRIPTION	EACH
CHAMPAIGN COUNTY: RURAL		
258+20.12	S. N. 010-0181	0.9
259+40.22	S. N. 010-0181	0.9
TOTAL =		1.8

542A0220 PIPE CULVERTS, CLASS A, TYPE 1 15"

STATION	TO	STATION	DESCRIPTION	FOOT
DOUGLAS COUNTY: RURAL				
149+50.00		151+03.72	S. N. 021-0041	153.72
TOTAL =				153.72
FINAL TOTAL =				154.0

542A0229 PIPE CULVERTS CLASS A, TYPE 1 24"

STATION	TO	STATION	DESCRIPTION	FOOT
CHAMPAIGN COUNTY: RURAL				
257+00.00		258+20.12	S. N. 010-0181	120.12
259+40.22		260+50.00	S. N. 010-0181	109.78
258+20.12, 3.5' LT		258+20.12, 9.5' LT	S. N. 010-0181	6.00
258+20.12, 3.5' RT		258+20.12, 9.5' RT	S. N. 010-0181	6.00
259+40.22, 3.5' LT		259+40.22, 9.5' LT	S. N. 010-0181	6.00
259+40.22, 3.5' RT		259+40.22, 9.5' RT	S. N. 010-0181	6.00
1017+61.00		1018+21.00	S. N. 010-0156	60.00
CHAMPAIGN COUNTY: URBAN				
350+97.07		352+00.00	S. N. 010-0176	102.93
TOTAL =				416.83
FINAL TOTAL =				417.00

60226270 RESTRICTED DEPTH MANHOLE 7 FOOT DIAMETER, TYPE 1 FRAME, CLOSED LID

STATION	DESCRIPTION	EACH
DOUGLAS COUNTY: RURAL		
151+03.72	S. N. 021-0041	1.0
CHAMPAIGN COUNTY: RURAL		
1017+61.00	S. N. 010-0156	1.0
TOTAL =		2.0

60500090 REMOVE INLETS TO MAINTAIN FLOW

STATION	DESCRIPTION	EACH
DOUGLAS COUNTY: RURAL		
151+03.72	S. N. 021-0041	1.0
CHAMPAIGN COUNTY: RURAL		
258+20.12	S. N. 010-0181	2.0
259+40.22	S. N. 010-0181	2.0
1017+61.00	S. N. 010-0156	1.0
CHAMPAIGN COUNTY: URBAN		
350+97.07	S. N. 010-0176	1.0
TOTAL =		7.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\p\projects\d514406\108\70628\sheet12.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
Sheet 12 of 13
 SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 03/24/07 CHECKED BY: M.L.B.