

# SUMMARY OF QUANTITIES

RURAL  
 STA. 427+00.00  
 TO STA. 694+00.00  
 90% FED.  
 10% STATE

| CODE NO. | DESCRIPTION  | CONSTRUCTION TYPE CODE: | UNIT   | TOTAL QUANTITY | SFTY-3J  | SFTY-3N  |
|----------|--|-------------------------|--------|----------------|----------|----------|
|          |  |                         |        |                | QUANTITY | QUANTITY |
| X0325764 | HOT-MIX ASPHALT REMOVAL, SPECIAL                   |                         | SQ YD  | 96.0           | 0.0      | 96.0     |
| 20200100 | EARTH EXCAVATION                                   |                         | CU YD  | 20.0           | 20.0     | 0.0      |
| 20400800 | FURNISHED EXCAVATION                               |                         | CU YD  | 165.0          | 165.0    | 0.0      |
| 21400100 | GRADING AND SHAPING DITCHES                        |                         | FOOT   | 500.0          | 0.0      | 500.0    |
| 25000200 | SEEDING, CLASS 2                                   |                         | ACRE   | 0.8            | 0.4      | 0.4      |
| 25000400 | NITROGEN FERTILIZER NUTRIENT                       |                         | POUND  | 72.0           | 36.0     | 36.0     |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT                     |                         | POUND  | 72.0           | 36.0     | 36.0     |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT                      |                         | POUND  | 72.0           | 36.0     | 36.0     |
| 25100115 | MULCH, METHOD 2                                    |                         | ACRE   | 0.8            | 0.4      | 0.4      |
| 28000255 | TEMPORARY EROSION CONTROL SEEDING                  |                         | ACRE   | 0.8            | 0.4      | 0.4      |
| 28000300 | TEMPORARY DITCH CHECKS                             |                         | EACH   | 16.0           | 16.0     | 0.0      |
| 28000400 | PERIMETER EROSION BARRIER                          |                         | FOOT   | 800.0          | 800.0    | 0.0      |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED                   |                         | POUND  | 920.0          | 613.3    | 306.7    |
| 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A                |                         | FOOT   | 3250.0         | 3,250.0  | 0.0      |
| 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6                   |                         | EACH   | 4.0            | 4.0      | 0.0      |
| 63100089 | TRAFFIC BARRIER TERMINAL, TYPE 6B                  |                         | EACH   | 10.0           | 10.0     | 0.0      |
| 63100167 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) |                         | EACH   | 3.0            | 3.0      | 0.0      |
| 63100169 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)  |                         | EACH   | 13.0           | 13.0     | 0.0      |
| 63200310 | GUARDRAIL REMOVAL                                  |                         | FOOT   | 4000.0         | 4,000.0  | 0.0      |
| 63400105 | GUARD POSTS  |                         | EACH   | 40.0           | 0.0      | 40.0     |
| 63400205 | GUARD POSTS REMOVAL                                |                         | EACH   | 54.0           | 0.0      | 54.0     |
| 67000200 | ENGINEER'S FIELD OFFICE, TYPE A                    |                         | EACH   | 3.0            | 1.5      | 1.5      |
| 67100100 | MOBILIZATION                                       |                         | L SUM  | 1.0            | 0.5      | 0.5      |
| 70100700 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701406    |                         | L SUM  | 1.0            | 0.5      | 0.5      |
| 78200410 | GUARDRAIL MARKERS, TYPE A                          |                         | EACH   | 64.0           | 64.0     | 0.0      |
| 78201000 | TERMINAL MARKER - DIRECT APPLIED                   |                         | EACH   | 16.0           | 16.0     | 0.0      |
| X7015005 | CHANGEABLE MESSAGE SIGN                            |                         | CAL DA | 28.0           | 14.0     | 14.0     |
| XX002909 | CLASS SI CONCRETE                                  |                         | CU YD  | 55.9           | 37.3     | 18.6     |
| Z0013300 | CONCRETE REMOVAL (SPECIAL)                         |                         | SQ YD  | 212.0          | 0.0      | 212.0    |
| Z0030150 | IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3 |                         | EACH   | 10.0           | 0.0      | 10.0     |
| Z0056220 | SAND MODULE IMPACT ATTENUATOR TO BE REMOVED        |                         | EACH   | 150.0          | 0.0      | 150.0    |

\* SPECIALITY ITEMS

PLOT DATE : 5/28/2007  
 FILE NAME : 44000000.dwg  
 PLOT SCALE : 1/8" = 1'-0"  
 USER NAME : jkennedy

△ - Revised 5-25-07