

CONTRACT NO. 72798

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	1,21RS-4	MASON	44	44
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

INCIDENTAL HOT-MIX ASPHALT SCHEDULE

DESCRIPTION	STATION	PROPOSED			AGGR. ENTR.		HMA. ENTR.		SIDE RD.		TOTAL (TON)	Aggr. Shldr AREA (SQ FT)	Bit Surf Rem Butt Jt (SQ YD)		
		WIDTH (FOOT)	LENGTH (FOOT)	AVG. (FOOT)	AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)					
HMA MBT (no entr) (LT)	258+22.00 LT	20	7	1.875			189.00	2.21			2.21	93.00			
(2100 E) RT	258+66.07 RT	53	9	1.875					558.00	6.51	6.51	154.50	62.00		
(2130 E) LT	271+80.03 LT	51	9	1.875					540.00	6.30	6.30	151.50	60.00		
HMA PE (LT)	280+97.00 LT	31	7	1.875			266.00	3.10			3.10	109.50			
HMA PE (w/MBT) (RT)	293+59.00 RT	16	15	1.875			753.00	8.79			8.79	135.00			
P. C. C. CE (RT)	305+50.00 RT	30													
HMA CE (RT)	310+88.00 RT	63	9	1.875			648.00	7.56			7.56	169.50			
(2200E) LT	311+54.84 LT	50	9	1.875					531.00	6.20	6.20	150.00	59.00		
HMA PE (RT)	312+37.00 RT	50	7	1.875			399.00	4.66			4.66	138.00	44.33		
HMA PE (LT)	327+00.00 LT	38	7	1.875			315.00	3.68			3.68	120.00			
HMA PE (w/MBT) (LT)	328+60.00 LT	18	15	1.875			783.00	9.14			9.14	138.00			
HMA PE (w/MBT) (LT)	358+47.00 LT	16	15	1.875			753.00	8.79			8.79	135.00			
HMA MBT (no entr) (LT)	362+34.00 LT	20	7	1.875			189.00	2.21			2.21	93.00			
AGG PE (RT)	362+52.00 RT	25	7	3.5	224.00	4.88					4.88	100.50			
AGG PE (RT)	363+04.00 RT	18	7	3.5	175.00	3.81					3.81	90.00			
HMA MBT (w/MBT) (LT)	366+71.00 LT	18	15	1.875			783.00	9.14			9.14	138.00			
HMA PE (RT)	367+08.00 RT	37	7	1.875					308.00	3.59	3.59	118.50			
HMA MBT (no entr) (LT)	370+53.00 LT	20	7	1.875			189.00	2.21			2.21	93.00	21.00		
HMA CE (RT)	370+72.00 RT	40	9	1.875			441.00	5.15			5.15	135.00	49.00		
HMA CE (RT)	373+34.00 RT	60	9	1.875			621.00	7.25			7.25	165.00			
HMA MBT (no entr) (LT)	373+53.00 LT	20	7	1.875			189.00	2.21			2.21	93.00			
HMA CE (RT)	373+34.00 RT	60	9	1.875			621.00	7.25			7.25	165.00			
HMA MBT (no entr) (LT)	373+53.00 LT	20	7	1.875			189.00	2.21			2.21	93.00			
HMA PE (RT)	399+64.00 RT	45	7	1.875					364.00	4.25	4.25	130.50			
HMA MBT (no entr) (LT)	399+64.00 LT	20	7	1.875			189.00	2.21			2.21	93.00			
(2400E) RT	415+38.97 RT	55	9	1.875					576.00	6.72	6.72	157.50	64.00		
(2400E) LT	415+38.97 LT	55	9	1.875					576.00	6.72	6.72	157.50	64.00		
HMA MBT (w/MBT) (LT)	468+67.00 LT	25	15	1.875			888.00	10.36			10.36	148.50			
(TR 2500E) RT	468+73.09 RT	48	9	1.875					513.00	5.99	5.99	147.00	57.00		
(TR 2600E) RT	521+68.45 RT	51	9	1.875					540.00	6.30	6.30	151.50	60.00		
(TR 2600E) LT	521+68.45 LT	52	9	1.875					549.00	6.41	6.41	153.00	61.00		
(TR 2670E) LT	560+64.34 LT	35	9	1.875					396.00	4.62	4.62	127.50	44.00		
HMA CE (RT)	568+40.00 RT	35	9	1.875			914.50	10.67			10.67	127.50	101.61		
HMA CE (RT)	569+15.00 RT	35	9	1.875			914.50	10.67			10.67	127.50	101.61		
HMA PE (LT)	569+07.00 LT	23	7	1.875			734.50	8.57			8.57	97.50	81.61		
HMA CE (RT)	569+07.00 RT	35	9	1.875			914.50	10.67			10.67	127.50	101.61		
SECTION ENDS	572+47.60														
LIMITS OF IMPROVEMENT	572+82.60														
Subtotal (pg 3) =							399.00	8.69	11,883.00	138.64	5,451.00	63.60	210.92	4,524.00	1,031.78
Total =							2,205.00	57.82	25,941.57	297.77	14,524.77	157.46	513.05	9,975.00	2,974.70

* QUANTITIES HAVE INCLUDED MAILBOX TURNOUTS WHICH SHALL BE BROUGHT UP TO GRADE USING INCIDENTAL HOT-MIX ASPHALT SURFACING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS FOR RURAL ENTRANCE, MAILBOX TURNOUT & SIDE ROAD
 SHEET 5 OF 5
 SCALE: VERT. DRAWN BY: CAD
 HORIZ. CHECKED BY: JCN
 DATE: DECEMBER 2, 2005

PLOT DATE = 3/22/2007
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = jcn