F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(9,10,11) RS-3	SCHUYLER	23	3
STA. 438+51		TO STA. 388+80		
FED. ROAD DIST. NO. 6	ILLINOIS	FED. AID PROJECT		

CONTRACT 72838

SUMMARY OF QUANTITIES				80% FEDERAL 20% STATE
				ROADWAY
CODE NO	ITEM	UNIT	TOTAL	1000
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	198	198
20400800	FURNISHED EXCAVATION	CUYD	40	40
35800100	PREPARATION OF BASE	SQYD	719	719
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	15	15
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	37	37
40600300	AGGREGATE (PRIME COAT)	TON	187	187
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3,884	3,884
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQYD	1,088	1,088
40600990	TEMPORARY RAMP	SQYD	31	31
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	9,099	9,099
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	326	326
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQYD	172	172
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	92,444	92,444
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	172	172
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQYD	320	320

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

U. S. ROUTE 24
F. A. P. ROUTE 317
SECTION (9, 10, 11) RS-3
SCHUYLER COUNTY

SCALE: DRAWN BY:
DATE: CHECKED BY: