F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(9,10,11) RS-3	SCHUYLER	23	4
STA. 438+51		TO STA. 388+80		
FED. ROAD DIST. NO. 6	ILLINOIS	FED. AID PROJECT		

CONTRACT 72838

SUMMARY OF QUANTITIES				80% FEDERAL 20% STATE
				ROADWAY
CODE NO	ITEM	UNIT	TOTAL	1000
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQYD	140	140
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,953	3,953
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQYD	2,201	2,201
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	500	500
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	700	700
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,682	10,682
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	86,698	86,698
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQFT	1,187	1,187
*78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	86,698	86,698

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

U.S. ROUTE 24
F.A.P. ROUTE 317
SECTION (9,10,11) RS-3
SCHUYLER COUNTY

SCALE: DRAWN BY:
DATE: CHECKED BY: